

---

## ***SCOPE OF WORK FOR BUILDING #4708 FLOORING INSTALLATION***

---

Site address: Building 4708 CAMP Cook, Ball, LA 71405 Date: 6 April 2016

Base Bid: Install new carpet floor tiles in classrooms and offices throughout building #4708

- 1) Contractor will remove all existing Carpet floor.
- 2) Contractor will not remove VCT tile under Carpet if any.
- 3) Contractor will clean and prepare surface to accept new Carpet tile.
- 4) Contractor will provide and install approximately 5787 square feet of 24"x24" commercial grade Shaw Wired Carpet Tile flooring (Style #54492) with the following specifications (91 ounces per sq yd, 8 stitches per inch, pile height of .190, solution dyed nylon, and lifetime performance warranty) or equal. (Contractor to verify quantity.)
- 5) Contractor will submit color samples to the Project Manager for tile color/style selection.
- 6) Contractor will remove existing Vinyl sanitary cove base, and install new sanitary Vinyl cove base after Carpet tiles are installed, Project Manager will select color.
- 7) Owner will remove all furniture from classrooms.
- 8) Contractor will add maximum of 5% of the total square feet of patch/Underlay/Leveler to price of project.

Alternate #1: Contractor will supply owner with 10% replacement carpet tile for building #4708.

### General Notes:

A preconstruction meeting will be scheduled prior to start of the project. A materials/equipment storage area (if required) will be designated by the Project Manager during the course of the preconstruction meeting.

All work performed must meet, or exceed OSHA, parish, state & local codes. All work must comply with SMD safety and environmental requirements. Contractor will ensure work area is clearly marked with safety barriers, flagging, and signage around the work site as required.

No changes to the project will be allowed, nor will the contractor be paid for any additional work unless an approved Change Order is formally requested and approved in advance. Site visit is required.

Contractor will conduct daily site clean up to ensure a clear work area as well as follow all safety guidelines. All debris and excess material must be disposed of by the contractor off of the project site and off of Camp Cook properly. Contractor must obtain authorization for placement of contractor provided dumpster with the project manager if needed.

Contractor will complete all work within 60 days.

---

***SCOPE OF WORK FOR BUILDING #4708 FLOORING INSTALLATION***

---

**Project Manager:**

Name : MSG Joseph Cole

Address: Bldg, 420 F St.

Camp Beauregard,

Pineville, LA 71360

Phone Number: 318-641-5431

Email: [joseph.g.cole4.mil@mail.mil](mailto:joseph.g.cole4.mil@mail.mil)