

**Purchasing Office**

P.O. Box 2052  
Thibodaux, LA 70310  
985.448.4038  
Fax: 448.4921

**NICHOLLS**  
STATE UNIVERSITY

**ADDENDUM NO 1  
FOR  
NICHOLLS STATE UNIVERSITY  
THIBODAUX, LOUISIANA  
06/03/2016  
PAGE 1 OF 1**

**Bid SB01705 – Contract for Chiller Maintenance Services  
Bid Due at 3:00 PM on 06/07/2016**

**Purpose of Addendum:**

Provide additional information, answer questions, provide additional specifications, provide revised bid form, provide acceptable equipment requested to be prior approved.

Provide revised specification pages 3 and 4 that provides the list of buildings and chiller serial numbers and model numbers.

RECEIPT OF ADDENDUM SHOULD BE ACKNOWLEDGED WITH THE RESPONSE TO THE BID. FAILURE TO ACKNOWLEDGE ADDENDA MAY BE CAUSE FOR BID NOT TO BE CONSIDERED.

  
Terry G. Dupre  
Director of Purchasing

**SPECIFICATIONS**  
**Nicholls State University**  
**Thibodaux, LA**  
**Chiller Service Contract**  
**Page 3 of 4**

**VI. List of Buildings and Chiller Serial Numbers and Model Numbers:**

**Section I: McQuay Centrifugal Chillers:**

Ellender Library                      SN 5ZD81012-01                      Model No. PHH063 – 200 Tons

**SECTION II: York Centrifugal and Scroll Chillers**

Peltier Hall – Centrifugal    SN SLCM-454730 - Model No. YKPBNC1-CUC - 640 Tons

Elkins Hall – Scroll    Model No. YCAL0050SC17 – Four (4) Compressors – 50 Tons

Elkins Hall – Scroll    Model No. YCAL0050SC17 – Four (4) Compressors – 50 Tons

Elkins Hall – Scroll    Model No. YCAL0050SC17 – Four (4) Compressors – 50 Tons

Elkins Hall – Scroll    Model No. YCAL0050SC17 – Four (4) Compressors – 50 Tons

Picciola Hall – Scroll    Model No. YCAL0040SC17 – Four (4) Compressors – 40 Tons

Galliano Hall – Scroll    Model No. YCAL0080EX17 – Four (4) Compressors – 80 Tons

Lanny Ledet – Scroll    Model No. YLAA03136SE46XFESD – 130 Tons

Lanny Ledet – Scroll    Model No. YLAA03136SE46XFESD – 130 Tons

Lindsley Hall – Screw – Model No. YLAA0058GHE17XEFBSDT – Two (2) Compressors – 50 Tons

**SECTION III: Carrier Centrifugal and Screw Chillers**

Peltier Hall – Centrifugal – Model No. 19XR-5050443DDS64 – SN 2998J58468 – 640 Tons

Ellender Library – Screw – Model No. 30HXC206R640 – Three (3) Compressors – 200 Tons

Ayo Hall – Screw – Model No. 30HXC146R630KA – Two (2) Compressors – 150 Tons

Ayo Hall – Screw – Model No. 30HXC146R630KA – Two (2) Compressors – 150 Tons

**SECTION IV: Dunn-Bush Reciprocating and Screw Chillers**

Duhe' Building – Reciprocating – Model No. ADCRB080D – Two (2) Compressors – 80 Tons  
(Houma)

Gouaux Hall – Screw – Model No. WCHDX130160R – Two (2) Compressors – 260 Tons

Gouaux Hall – Screw – Model No. WCHDX130160R – Two (2) Compressors – 260 Tons

**SPECIFICATIONS**  
**Nicholls State University**  
**Thibodaux, LA**  
**Chiller Service Contract**  
**Page 4 of 4**

**VI. List of Buildings and Chiller Serial Numbers and Model Numbers – Continued:**

**SECTION V: Trane Screw Chillers and Worthington Reciprocating Chillers**

North Babington – Model No. GCH501-5-22PW-313 – One (1) Compressor – 80 Tons

Talbot Hall – Screw – Model No. RTAA-125A-YQ01-A380-KNB – Two (2) Compressors – 150 Tons

Talbot Hall – Screw – Model No. RTAA-125A-YQ01-A380-KNB – Two (2) Compressors – 150 Tons

Barker Hall – Screw – Model No. RTAA-070A-YT01-A300-6KNB – Two (2) Compressors – 60 Tons

Student Union–Screw–Model No. RTHD-UB1A-XHOU-AB1A-2RAL-B1A2–One (1) Compressor 168 Tons

Ellender Residence Hall – Screw – Model No. GRAM100F2C02AXA – Two Compressors – 100 Tons  
Installed 2011 – under 5-year warranty

Ellender Residence Hall – Screw – Model No. GRAM100F2C02AXA – Two (2) Compressors – 100 Tons  
Installed 2001 – under 5-year warranty

Caillais Recreation Center – Screw – Model No. RTAC1554UVON – Two (2) Compressors – 155 Tons  
Installed 2012 – under 5 year warranty

Caillais Recreation Center – Screw – Model No. RTAC1554UVON – Two (2) Compressors – 155 Tons  
Installed in 2012 – under 5 year warranty

Stopher Gymnasium – Screw – Model RTAC1704 – 170 Ton

Stopher Gymnasium – Screw – Model RTAC1704 – 170 Ton

NOTE: Contractor will be required to perform annual stop inspections on the chillers that are under warranty. All service work shall be performed under the current warranty.