

1. Furnish all labor, tools, materials, and equipment to re-roof Psychology Building located on the grounds of Pinecrest Supports and Service Center as per bid document specifications.
2. Location: 195 Faulk Avenue
3. Scope of work:

Install new 50 year CertainTeed Max Def Weathered Wood or equal; Final color will be determined by Maintenance Manager.

All shingles must be hand nailed with minimum of 1-1/4 hot dipped galvanized roofing nails: minimum 6 nails per shingle ***no air nailing shall be allowed*** No electrogalvanized nails***

Valleys shall be Woven Valleys. Note: Closed Cut valleys and flashing will **not** be allowed!

Remove and replace all old shingles, felt, vents, boots, nails and valley flashing. Install new style D drip edges minimum 1 3/4 inches wide around entire building including rakes.

Install new lead boot jacks on all roof vents.

Replace roof jacks around heater vent pipes with new.

Replace electrical roof jack with split type jack. Power will not be disconnected.

Remove existing roof vents patch decking and install new 24" turbines, color to match Roofing.

Install Manufactures approved felt, felt to be a minimum of 30 lb. felt.

Moisture guard shall be installed at all penetrations, ridges, walls, eaves, vents, valleys and rakes.

If manufacturer specifications exceed minimum requirements listed, the manufacturer specifications must be used.

Flashing to be lapped a minimum of 2 inches.

Work area to be kept safe at all times. This is to include, barricades, flagging, fences, and personnel needed. All safety procedures will be reviewed and approved by Maintenance Manager.

Contractor will use pads as needed when driving off road to avoid damage to grass areas around building. All damage to grass areas will be repaired.

Flashing and trim will be installed per National Roofing Contractors Association Standards.

NOTE: All amounts are Approximate and must be verified by the bidder.

4. Contractor responsible for trash disposal. No dumpster will be provided.
5. Roof shall be installed to 130 MPH wind rating.
6. All work must meet State and Local Building Codes and be in accordance with National Roofing Contractors Association Standards.
7. All contractors must be manufacturer certified
8. Warranty: Warranty to be CertainTeed Sure Start Plus 4-Star coverage of equal
9. Planning and Scheduling

After notification by purchase order that the contractor has been awarded the contract, the contractor shall contact Wymon Terrell, maintenance manager.

Before entering agency grounds to commence work, the contractor must check in with the maintenance department secretary "each" day before commencing work.

Work hours to be 7:30AM to 4:00PM Monday through Friday unless approved by Maintenance Manager.

10. Job Site Visit: Contact Wymon Terrell or John Bennett @ (318) 641-2288