

1. Furnish all labor, tools, materials, and equipment to re-roof State buildings #06941, #06867, #06968, #06931 located on the grounds of Pinecrest Supports and Service Center as per bid document specifications.

2. Location: PSSC
3. Scope of work:

Install new 50 year CertainTeed Burnt Sienna shingles or equal; Final color will be determined by Maintenance Manager.

All shingles must be hand nailed with minimum of 1-1/4 hot dipped galvanized roofing nails: minimum 6 nails per shingle \*\*\*no air nailing will be allowed\*\*\* No electrogalvanized nails\*\*\*

Valleys will be Woven Valleys. Note: Closed Cut valleys and flashing will *not* be allowed!

Remove all old shingles, felt, vents, boots, nails and valley flashing.

Install new style D drip edges minimum 1 3/4 inches wide around entire building including rakes.

Install new lead boot jacks on all roof vents.

Replace roof jacks around heater vent pipes with new.

Replace electrical roof jack with split type jack. Power will not be disconnected.

Replace existing roof vent with 24" new turbines, color to match Roofing.

Install Manufactures approved felt, felt to be a minimum of 30 lb. felt.

Moisture guard shall be installed at all penetrations, ridges, walls, eaves, vents, valleys and rakes.

Remove existing sky lights and patch decking for new shingles to be installed. Replace high side trim with new L-shaped hemmed 3"x3" trim color to match shingles. State building # 06968 only.

If manufacturer specifications exceed minimum requirements listed, the manufacturer specifications must be used.

Flashing to be lapped a minimum of 2 inches.

Work area to be kept safe at all times. This is to include, barricades, flagging, fences, and personnel needed. All safety procedures will be reviewed and approved by Maintenance Manager.

Contractor will use pads as needed when driving off road to avoid damage to grass areas around building. All damage to grass areas will be repaired.

Flashing and trim will be installed National Roofing Contractors Association Standards.

**NOTE:** All amounts are Approximate and must be verified by the bidder.

4. Contractor responsible for trash disposal. No dumpster will be provided.
5. Roof shall be installed to 130 MPH wind rating.
6. All work must meet State and Local Building Codes and be in accordance with National Roofing Contractors Association Standards.
7. All contractors must be manufacturer certified
8. **Warranty:**  
Contractor to supply 20-year NDL (no dollar limit) and 50-year pro-rated manufacturer warranty certificate.
9. **Planning and Scheduling**  
After notification by purchase order that the contractor has been awarded the contract, the contractor shall contact Wymon Terrell, maintenance manager.  
Before entering agency grounds to commence work, the contractor must check in with the maintenance department secretary "each" day before commencing work.  
Work hours to be 7:30AM to 4:00PM Monday through Friday unless approved by Maintenance Manager.

10. Job Site Visit: Contact Wymon Terrell or John Bennett @ (318) 641-2288