



ADDENDEUM 1
AIR COOL CHILLER REPLACEMENT
AT
STADIUM SUPPORT BUILDING
Bid #50018-160008

Bid Open

July 15, 2016 @ 10:00 a.m.

1. Alternate pump specification and installation
 - a. N/A
2. Compressor type
 - a. Scroll type specified in bid document
 - b. Include an alternate bid for screw type
3. Suction Service Valves
 - a. Add to chiller
4. Completion time
 - a. 8-10 Weeks (from date of order)
5. Delete section on page 30
 - a. Part 1 (General)

6. Delete section on page 31
 - a. Part 2 (Products)
7. Delete section on page 32
 - a. Part 3 (Execution)
8. Delete section on page 32
 - a. 3.2 (Pump installation)
9. Delete on page 25 (Demolition)
 - a. Bullets 3 and 4
10. Delete on page 26 (Construction Requirements)
 - a. Items A & B
11. Installation of heat tape to supply and return line (from chiller to ground)
12. Acceptable Manufacturers
 - a. Daikin Applied Model AGC160
 - a. Multistack ASP170
 - c. Carrier 30RBS160
 - d. York Model YLAA

Please sign and return with bid:
