



Attachment B – Specifications  
RFx No. 3000006132 Title: BSL3 Certification  
LDH – Office of Public Health

---

To furnish all labor, meters, tools, materials, supplies and supervision to:

- 1) Certify the BSL3 areas of the Laboratory by the guidelines specified by the CDC/NIH/WHO
- 2) Review all Laboratory Standard Operating Procedure documentation
- 3) Certification will begin with lab testing of envelope leakage, temperature control, electrical load testing, plumbing and vacuum system testing, and operating differential testing.
- 4) Certification will conclude with air distribution testing, HEPA filter testing, alarm testing, access testing, and finally system failure testing.
- 5) The data will be compiled into a certification report.
- 6) Any deficiencies will be addressed and corrected if possible, otherwise they will be noted to OPH as soon as possible.
- 7) Johnson Controls Inc. (JCI) and Office of State Buildings (OSB) will also be coordinated with the AHU testing and generator testing.