

Pinecrest Support and Services Center
100 Pinecrest Dr.
Pineville La. 71360
Home 216/Home 217/Home 314

This solicitation is for the Rebid: Installation of Aluminum Canopies located at 100 Pinecrest Dr. Pineville La. 71360, Home 216, Home 217, and Home 314. This solicitation is a rebid of 3000014058. A jobsite certification form can be submitted for RFX 3000014058 in lieu of 3000014480. The job is to be performed in accordance with the enclosed scope of work.

Scope of work:

- The Contractor shall furnish all labor, materials, tools, and equipment necessary for three canopies:
 - Home 216; one 20 feet x 24 feet canopy.
 - Home 217; one 20 feet x 24 feet canopy.
 - Home 314; one 14 feet x 35 feet canopy.
- Canopies shall be Superior Metal Products Company, Section 10530- Protective covers or equal.
- Canopy colors shall be: post painted medium bronze, c-beam painted medium bronze, gutter painted medium bronze, w-pan painted white on top and cream on the bottom to match existing.
- The Post shall be offset for walkways, as needed. The Contractor shall confirm location of the post with PSSC at job site visit.
- The low side of canopy shall have eight (8) foot clearance minimum including beams.
- All metal used for connecting the beam shall be painted to match existing.
- All holes shall be hand dug, care shall be used to avoid damage to any unknown units.
- All canopies shall have a minimum of 1/4 inch fall per foot.
- The Contractor shall not cause damage to grassy areas. If damaged, all grass areas should be restored to its original condition.
- Flashing shall be supplied and installed to match existing homes, along the roof where the canopy is attached to the building.
- The Contractor shall confirm all measurements at job site visit.

Delivery and Storage:

- The Contractor is responsible for all delivery and storage.

Planning and Scheduling:

- The Contractor shall contact the Maintenance Manager to receive workschedule.
- A notice of working days shall be given by the Maintenance Manager before work is to commence.
- Before entering Agency grounds Contractor shall check in with the Maintenance Department Secretary "each" day before commencing work.
- Working hours are 7:30 AM to 4:00 PM Monday through Friday unless changed by Maintenance Manager.