



JEFFERSON PARISH

DEPARTMENT OF PURCHASING

CYNTHIA LEE SHENG
PARISH PRESIDENT

RENNY SIMNO
DIRECTOR

March 29, 2023

ADDENDUM # 1

Bid Number: 50-00141138

Receipt Date: April 4, 2023
Postponed to Date: N/A

Description of Bid: Two (2) year contract for Street Lighting Maintenance for The Westbank Harry Lee Expressway for the Jefferson Parish Engineering Department

REVISION:

- Please see the updated Lighting Inventory sheet
- Please see the updated Articles of Description sheets

***** DEADLINE FOR QUESTIONS HAS PASSED*****

*****PLEASE REMEMBER TO ACKNOWLEDGE THIS ADDENDUM ON YOUR BID SUBMISSION *****

Sincerely,

A handwritten signature in blue ink, appearing to read "Shanna Folse".

Shanna Folse, Buyer II
Jefferson Parish Purchasing Department

Bidders must acknowledge all addenda on the bid form. Bidder acknowledges receipt of this addendum on the bid form by indicating the addendum number listed above. Failure to list each addenda number on the bid form will result in bid rejection.

This addendum is a part of the contract documents and modifies the original bidding documents and specifications. The contents of this addendum shall be included in the contract documents. Changes made by this addendum shall take precedence over the documents of earlier date.

JOSEPH S. YENNI BUILDING - 1221 ELMWOOD PARK BLVD - SUITE 404 - JEFFERSON, LA 70123 - PO BOX 10242 JEFFERSON, LA 70181-0242
OFFICE 504.364-2678

GENERAL GOVERNMENT BUILDING - 200 DERBIGNY ST - SUITE 4400 - GRETNA, LA 70053 - PO BOX 9 - GRETNA - LA 70054
OFFICE 504.364.2678

EMAIL: PURCHASING@JEFFPARISH.NET

WEBSITE: WWW.JEFFPARISH.NET

Westbank-Harry Lee Expressway Lighting Inventory Hwy 90B

	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	
1																				
2						High Mast	Low Mast Sing	Low Mast Doub	30 Ft Single Poles	30 Ft Doub Mast	35 Ft Single Poles	35 Ft Doub Mast	40Ft Sing Mast	150 Watts	175 Watts	250 Watts	400 Watts	1000 Watts	Total Lights	
3	High Pressure Sodium – Unmetered																			
4																				
5																				
6	Westbank Expressway - Segnette Blvd to Hwy 90										86	7			100					100
7	Westbank Expressway - Segnette Blvd to Terry Pkwy										469	104			204	473				677
8	Westbank Expressway - High Mast Parish Line										1								4	4
9	Westbank Expressway - Drop Lights													84						84
10	Westbank Expressway - Bridge Column Lights														88					88
11	Westbank Expressway - Roadway Lights											71					71			71
12	Roadway Subtotals																			
13	Others																			
14	Total																			
15						1	0	0	0		626	111	0	84	0	392	544	4	1024	
16	Metal Halide – Unmetered																			
17																				
18	Total																			
19																			0	
20	Metal Halide – Metered																			
21	Westbank Expressway - Bike Path Lights														273					
22																				
23																				
24	Total																			
25															273		0	0	273	
26	LED – Unmetered																			
27	Whitney Ave-Gretna											51			51					51
28																				
29	Total																			
30																			0	
31	LED- Commercial 200 watt, 120/240v																			
32																				
33	Total																			
34																			0	
35	LED- Commercial 200 watt, 240/480v																			
36																				
37	Total																			
38																0			0	
39	Total Owned By Jefferson Parish																			
40						1	0	0	0		677	111	0	84	273	443	544	4	1348	
41	All Numbers are approximate																			
42	Table may not include lighting under construction																			

Appendix 2

Labor and and Materials-Articles of Description

ITEM NUMBER	QUANTITY	U/M	C/C	ARTICLES OF DESCRIPTION	UNIT PRICE QUOTE	TOTALS
1	1	EA		0010 TWO (2) YEAR CONTRACT FOR THE WESTBANK/HARRY LEE EXPRESSWAY ROADWAY LIGHTING MAINTENANCE AND REPAIR - Unit Maintenance cost for routine maintenance and repair, including Lamp, Ballast, Photo Control, Fuses, Fixture, Hand hole cover and/or Pole wiring. The current number of Parish-owned Westbank Expressway Hwy 90B light units is approximately 1348 (See inventory summary). Unit Price quoted shall be as a Re-Lamp Per Each Pole Basis cost to undertake all routine maintenance and repair on street light units as set forth in the attached specification summary, Section G. The underground/overhead conduit circuits, pole replacement and foundations shall be issued as a Special Work Order or as needed basis. The approximate number of work orders per month has not been determined as of date and shall be issued on an "as needed basis" . However, no adjustment shall be made to the Unit cost.		
2	8	HR		0020 Traffic Control - Police Detail		
3	8	HR		0030 - Pole Pickup from Jefferson parish Warehouse		
4	8	HR		0040 - Supervisor for oversight and coordination when using approved subcontractors and/or Special Work Orders.		
5	8	HR		0050 - Labor - Licensed Electrician		
6	8	HR		0060 - Labor - Mechanic		
7	8	HR		0070 - Labor - Laborer		
8	8	HR		0080 - Equipment Operator (CDL)		
9	8	HR		0090 - Bucket truck capable of reaching 45Ft with tools and equipment necessary to undertake work in conjunction with the repair and maintenance of a street lighting system.		
10	1	EA		0100 - Knocked down Poles/Pick up for this contract term. See Section G, 2-j items 1 & 2, also Section I, 3-b Downed poles.		
11	8	HR		0110 - Backhoe and loader combination (If rented, equipment shall be charged at direct cost)		
12	8	HR		0120 - Truck mounted crane (if rented, equipment shall be charged at direct cost		

Appendix 2

Labor and and Materials-Articles of Description

13	8	HR	0130 - Service truck equipped with tools and equipment necessary to undertake work in conjunction with the repair and maintenance of a street lighting system		
14	8	HR	0140 - Flatbed truck (If rented, equipment shall be charged at direct cost)		
15	8	HR	0150 - Backhoe Loader Transport (if rented, equipment shall be charged at direct cost)		
16	8	HR	0160 - Air compressor (If rented, equipmetn shall be charged at direct cost)		
17	8	HR	0170 - Welding machine (If rented, equipment shall be charged at direct cost)		
18	100	LF	0180 - Directional underground borer - Shall be paid as per line item, cost per foot, for any boring in excess of 50 Ft. The contractor shall be responsible for the first 50 ft of cost as per Section F-Item 4-b.		
19	8	HR	0190 - Jack Hammer - per hour (if rented, equipment shall be charged at direct cost)		
20	8	HR	0200 Utility and/or pole trailer (If rented, equipment shall be charged at direct cost)		
21	5	EA	0210 - Leaning poles needing minimal adjustment		
22	1	EA	0220 - 100W HPS- M VOLT/480V Nema, Cobra Type III or Wallflasher Fixture with semi-cut-off precision refractor, with PE cell, including bulb.		
23	1	EA	0230 - 150W HPS- M VOLT/480V Nema, Cobra Type III or Wallflasher Fixture with semi-cut-off precision refractor, with PE cell, including bulb.		
24	1	EA	0240 - 250W- M VOLT/480V HPS Cobra American Electric Lighting, Type III Fixture 315 25S R3 DG with semi-cut-off precision refractor, with PE cell, including bulb.		
25	1	EA	0250 - 400W- M VOLT/480V HPS Cobra, American Electric Lighting, Type III Fixture 325 40S R3 DG with semi-cut-off precision refractor, with PE cell, including bulb.		
26	1	EA	0260 - 1000W High Mast Luminaire		
27	1	EA	0270 - 1000W-480V HPS Mogul Flagpole lights @ Terry Pkwy		
28	1	EA	0280 - LED Beacon Lights (120V) 3 each side of Harvey Canal Bridge		
29	1	EA	0290 - 70W-M VOLT/480V Ramp Lighting, MED Base		
30	1	EA	0300 - 150W HPS/MH M VOLT/480V HPS Hanging Pendant Lights, at Intersections		

Appendix 2

Labor and and Materials-Articles of Description

31	1	EA		0310 - 250W-480V MH-Mogul Bridge Column Lights		
32	1	EA		0320 - American Electric Lighting LED Cobra Type Fixture: ATBL C XXXXXX R3 480V 4K AO P7 PCLL LUMEN OUTPUT 22031, 200 WATTS		
33	1	EA		0330 - American Electric Lighting LED Cobra Type Fixture: ATB2 P602 R3 4K 480 Volt P7 PCLL LUMEN OUTPUT 30020, 196 WATTS		
34	1	EA		0340 - Hand Hole Covers, Universal Crossbar Compression Series- or equal.		
35	1	EA		0350 - Hubbell Power Systems Helical Screw-In Foundation Cat. No. T1121751, T1121215		
36	1	EA		0360 - QUAZITE BOX 12" X 12"		
37	1	EA		0370 - QUAZITE BOX 11" X 17"		
38	1	EA		0380 - NON FUSABLE BREAKAWAY HOLDER		
39	1	EA		0390 - FUSE HOLDER BREAKAWAY		
40	1	EA		0400 - Modular Cable Breakaway Assembly, MG2 fusible disconnect device		
41	1	EA		0410 - PEDESTAL MOUNT CONTROLLER		
42	1	EA		0420 - DISCONNECT STAINLESS STEEL 120V-240V 2POLE FUSABLE		
43	1	EA		0430 - DISCONNECT STAINLESS STEEL 600 VOLT 2 PH (FUSABLE)		
44	1	EA		0440 - Poles shall be seamless spun aluminum (Valmont 3408-45805T4D1SBF or equal, number description may vary), 40 mounting height. Note: All poles shall be round tapered and include factory installed vibration dampeners.		
45	1	EA		0450 - Poles shall be seamless spun aluminum (Valmont 2708-45806T4D2SBF or equal, number description may vary), 30-foot mounting height. Note: All poles shall be round tapered and include factory installed vibration dampeners.		
46	1	EA		0460 - HAPCO 6 foot clamp-mounted, single arm type or equal to receive the fixtures noted above.		
47	1	EA		0470 - HAPCO 8 foot clamp-mounted, single arm type or equal, to receive the fixtures noted above.		
48	1	EA		0480 - HAPCO 10 foot clamp-mounted, single arm type or equal) to receive the fixtures noted above.		
49	1	EA		0490 - Valmont 6 foot clamp-mounted, truss-type arm (Valmont 2TA0632CSBF or equal) to receive the fixtures noted above.		

Appendix 2

Labor and and Materials-Articles of Description

50	1	EA	0500 - Valmont 8 foot clamp-mounted, truss-type arm (Valmont 2TA0832CSBF or equal) to receive the fixtures noted above.		
51	1	EA	0510 - Valmont 10 foot clamp-mounted, truss-type arm (Valmont 2TA1032CSBF or equal) to receive the fixtures noted above.		
52	1	EA	0520 - Valmont TB-1 Breakaway Transformer Base		
53	1	EA	0530 - Valmont TB-2 Breakaway Transformer Base		
54	1	EA	0540 - Valmont TB-3 Breakaway Transformer Base		
55	1	EA	0550 - Bike Pathway Light Pole & Fixture, Whatley- RTA34-14-AB-BLK-SMS-FLD-BC1, W/STD HAND HOLE		
56	10	EA	0560 - Shades or Fixture lenses broken, damaged, vandalized or missing.		
57	1	EA	0570 - 100 Watt HPS Lamp		
58	1	EA	0580 - 150 Watt HPS Lamp		
59	1	EA	0590 - 175 Watt HPS Lamp		
60	1	EA	0600 - 250 Watt HPS Lamp		
61	1	EA	0610 - 400 Watt HPS Lamp		
62	1	EA	0620 - 1000 Watt HPS Lamp		
63	1	EA	0630 - 480 Volt Photo control		
64	1	EA	0640 - 100 HPS or LED COBB Lamp and Ballast replacement, CL-S38 30WATT 3500K, 4500 Lumens or Equal, See Parts List		
65	1	EA	0650 - 150 HPS or LED COBB Lamp and Ballast replacement, CL-S38 40WATT 3500K, 6000 Lumens or Equal, See Parts List		
66	1	EA	0660 - 175 HPS or LED COBB Lamp and Ballast Replacement, CL-S38 60 WATT 3500K, 9000 Lumens or Equal, See Parts List		
67	1	EA	0670 - 250 HPS or LED COBB Lamp and Ballast replacement, CL-S35-80W -10, 80 Watt, 3500K, 11200 Lumens or Equal, See Parts List		
68	1	EA	0680 - 400 HPS or LED COBB Lamp and Ballast replacement, CL-S35-110W-10, 110 Watt, 3500K, 16500 Lumens or Equal, See Parts List		
69	1	EA	0690 - 1000 Watt Ballast or LED Cobb Lamp replacement, May not be available		
70	2	EA	0700 - 5 Amp 600 Volt Bussman type fuses		
71	500	FT	0710 - SO, Soft rubber Type cord, 12/3 Cu - 600 Volt		

Appendix 2

Labor and and Materials-Articles of Description

72			0720 - NON-BIDDABLE ITEM (FOR BIDDING PURPOSES PLEASE LEAVE BLANK) THE COST OF ANY OTHER MISCELLANEOUS ITEMS NECESSARY FOR THE COMPLETION OF THIS CONTRACT SHALL BE APPROVED BY JEFFERSON PARISH, WHEN THE COST OF SAID ITEMS ARE IDENTIFIED AND QUOTED.		
73			0730 - NON-BIDDABLE ITEM (FOR BIDDING PURPOSES PLEASE LEAVE BLANK) SPECIAL WORK ORDER INVOICES: "NOT TO EXCEED0590 - NON-BIDDABLE ITEM (FOR BIDDING PURPOSES PLEASE LEAVE BLANK) THE COST OF ANY OTHER MISCELLANEOUS ITEMS NECESSARY FOR THE COMPLETION OF THIS CONTRACT SHALL BE APPROVED BY JEFFERSON PARISH, WHEN THE COST OF SAID ITEMS ARE IDENTIFIED AND QUOTED. COST ESTIMATE, MUST BE APPROVED BY JEFFERSON PARISH. (SECTION I, PART 2B)		

REVISED PER ADDENDUM #1