

UNIVERSITY of NEW ORLEANS

ADDENDUM NO. 2

FOR

MAIN ARENA CEILING TILE REPLACEMENT
LAKEFRONT ARENA EAST CAMPUS

NOTE:

**THIS ADDENDUM SHOULD BE ACKNOWLEDGED IN THE
APPROPRIATE BLANK ON THE PROPOSAL FORM.**

PREPARED BY

UNIVERSITY OF NEW ORLEANS

PURCHASING OFFICE

ADMINISTRATION ANNEX, ROOM 1004-G

LAKEFRONT - NEW ORLEANS - LOUISIANA - 70148

Bid #2843

PURCHASING REPRESENTATIVE: Troy Bacino, Assistant Director for Purchasing

PHONE(504)280-6172 FAX (504)280-6297 E-mail tabacino@uno.edu

UNIVERSITY REPRESENTATIVE: Brandt Daniels, Asst. General Manager or Drew Lytle
(504) 280-7171 E-mail: bpdaniel1@uno.edu
(504) 280-7261 E-mail: dslytle@uno.edu

Date: August 20, 2024

SP 5254

ADDENDUM NO. 2

SP5254 BTB2843

PAGE 1 OF 2

Bidders are informed that prior Bidding Documents for this project are modified, corrected and/or supplemented as herein enumerated. The following is hereby made a part of the Contract Documents:

Clarifications/Changes:

1. Specification Section 09510, Part 1 – General, 1.1 Description of Work: eliminate “insulation” from the paragraph. There is no existing insulation above the ceiling.
2. Specification Section 09510, Part 1 – General, 1.8 Extra Stock: Change “10 percent” to “1 percent” attic stock.
3. Specification Section 09510, Part 3 – Execution, 3.2 Installation, B: Remove sentence “Utilize existing retention clips to secure new ceiling tiles” to read “Existing retention clips shall be removed, no new retention clips are required”

Questions:

1. On top of attic stock, how likely is it that the university will keep unbroken tiles that are removed? Do these tiles need to be packaged up in any certain manner or turned over loose?
Answer: The contractor does not need to keep unbroken tile that will be removed. This statement pertains to only the new tile that is being installed if not used, separate from the attic stock. These can be handed over loose or in a box at the University Representative’s discretion.
2. Existing retention clips are very sporadic. What percentage of the area (or how many clips) should be considered to be reinstalled?
Answer: After review, the University will eliminate the need for the hold down clips to be reinstalled. Turn over any existing clips to the University Representative, these can be turned over in a box.
3. Please confirm that roll-off dumpster can be placed on the Main Arena floor with plywood protection underneath.
Answer: This is acceptable; however, roll-off dumpsters will need to be removed from the arena floor for any scheduled events and/or direction of University Representative.
4. Please confirm that a boom truck can be placed on the arena floor with mats/protection under outriggers.
Answer: This is acceptable; however, boom truck will need to be removed from the arena floor for any scheduled events and at direction of University Representative.

Attachments:

1. UNO Lakefront Arena Fall Event Schedule
 - a. For basketball games – day prior and day after for setup and removal of basketball floor
 - b. For concerts – two days for set up and one days for removal
 - c. No work can be performed one day prior to 10/22/24 basketball game for floor set up until morning of 10/31/24 for floor removal. Coordinate with University Representative.

- END -

UNO LAKERONT ARENA FALL EVENT SCHEDULE

9/13/2024 Paw Patrol Concert
9/14/2024 Paw Patrol Concert
9/15/2024 Paw Patrol Concert
9/15/2024 Athletics Meet the Teams
~~9/28/2024 Comedy Show PENDING~~
10/22/2024 Basketball Exhibition Game
10/30/2024 Basketball Exhibition Game
11/9/2024 Basketball - Homecoming vs TROY
11/15/2024 Tamia and Joe Concert
11/19/2024 UNO WBB EDUCATION DAY vs SO ALABAMA
11/22/2024 Maverick City Music Concert
12/7/2024 Concert Pending
12/7/2024 Tom Segura Concert
12/10/2024 LSUHSC Nursing Ceremony 10am
12/11/2024 LSUHSC Commencement 10am
12/12/2024 UNO Rehearsal 4pm
12/13/2024 UNO Commencement
12/17/2024 Delgado Commencement 10 AM
12/20/2024 Concert 12/28/2024 CONCERT Load-in/Tech Day
12/29/2024 CONCERT Night 1
12/30/2024 CONCERT Night 2
12/31/2024 CONCERT Night 3