December 2, 2024

Please find the following addendum to the below-mentioned QUOTE.

Addendum No.: 1

Quote#: 24-64-1

Project Name: St. Tammany Parish Artificial Reefs – Material Hauling

Quote Due Date: Thursday, December 5, 2024

GENERAL INFORMATION:

1. Please Delete Attachment G – Hauling Plan and Replace with Attachment G – Hauling Plan Revised. (Attached)

QUESTIONS & ANSWERS:

Question 1: Please clarify that the material is to be loaded (by bidder) at 38142 Hwy Dept Rd, Pearl River, LA 70452 and transported to 58026 East St., Slidell, LA 70460 (as shown on the map) or 3819 France Road New Orleans, LA 70126 (as stated in the specifications).

Answer 1: The material is to be loaded at 38142 Hwy. Dept. Rd and transported to 3819 France Road, New Orleans, LA.

Question 2: Will the bidder be responsible for stockpiling the material at the delivery address?

Answer 2: The bidder is responsible for stockpiling the material at the delivery address. Sheet 07, Note 1 of the attached drawings requires that the bidder coordinate the drop-off location with the property owner.



Question 3: Will the trucks be scaled for payment? Who will be responsible for scaling the

trucks and at what location will they be scaled

Answer 3: The contractor is responsible for scaling for payment. The contractor shall

provide daily truck tickets for material delivered to the drop-off site. See Sheet

02, Note 2, 3, and 4.

ATTACHMENTS:

1. Attachment G – Hauling Plan Revised.

<< End of Addendum # 1 >>






VICINITY MAP

NOT TO SCALE

ST.TAMMANY PARISH

GOOSE POINT ARTIFICIAL REEFS MATERIAL HAULING PLAN

PROJECT NO. 39130-1491 ST. TAMMANY PARISH, LOUISIANA SEPTEMBER 2024



Project Vicinity







PROJECTION: LOUISIANA STATE PLAN (SOUTH ZONE) GEO. DATUM: NAD83 / VERTICAL: NAVD88 GRID UNITS: US SURVEY FEET

GENERAL NOTES:

- 1. CONTRACTOR SHALL VISIT THE SITE PRIOR TO THE START OF CONSTRUCTION AND COMPLETELY INFORM HIMSELF RELATIVE TO THE EXISTING CONDITIONS.
- 2. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, EXISTING ELEVATIONS AND CONDITIONS ON THE PLANS PRIOR TO ORDERING MATERIAL, COMMENCEMENT OF CONSTRUCTION, AND PREPARATION OF SHOP DRAWINGS. THE ENGINEER SHALL BE NOTIFIED OF ALL DISCREPANCIES.
- 3. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS DURING THE PERFORMANCE OF THIS PROJECT. SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE ENGINEER AND THE OWNER ARE NOT RESPONSIBLE FOR SAFETY IN, ON, OR ABOUT THE PROJECT SITE, NOR FOR COMPLIANCE BY THE APPROPRIATE PARTY WITH ANY REGULATIONS RELATED THERETO.
- 4. CONTRACTOR SHALL TAKE REASONABLE MEASURES TO AVOID UNNECESSARY NOISE APPROPRIATE FOR THE AMBIENT SOUND LEVELS IN THE AREA DURING WORKING HOURS. ALL CONSTRUCTION MACHINERY AND VEHICLES SHALL BE EQUIPPED WITH PRACTICAL SOUND MUFFLING DEVICES, AND OPERATED IN A MANNER TO CAUSE THE LEAST NOISE, CONSISTENT WITH EFFICIENT PERFORMANCE OF THE WORK.
- 5. CONTRACTOR SHALL TAKE REASONABLE MEASURES TO AVOID UNNECESSARY DUST. SURFACES SUBJECT TO CREATING DUST SHALL BE KEPT MOIST WITH WATER OR BY APPLICATION OF CHEMICAL DUST SUPPRESSANT.
- 6. ACCESS TO THE PROJECT SITE FOR HEAVY MACHINERY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE OWNER AND/OR ENGINEER TAKE NO RESPONSIBILITY FOR EXISTING ROAD AND BRIDGE LOAD RATINGS. CONTRACTOR SHALL SUBMIT A MOBILIZATION PLAN TO THE ENGINEER FOR APPROVAL A MINIMUM OF 72 HOURS PRIOR TO ANY MOBILIZATION. ANY DAMAGES INCURRED DURING MOBILIZATION SHALL BE REPAIRED BY THE CONTRACTOR IN KIND AT NO COST TO THE OWNER AND TO THE SATISFACTION OF THE ENGINEER.
- 7. THE CONTRACTOR SHALL SATISFACTORILY MAINTAIN THE ENTIRE AREA WITHIN THE PROJECT DURING ITS DURATION.
- 8. THE CONTRACTOR'S MAINTENANCE RESPONSIBILITY INCLUDES, BUT IS NOT NECESSARILY LIMITED TO, MAINTAINING DRAINAGE AND REMOVING OF DEBRIS AND REMAINS, TO THE SATISFACTION OF THE ENGINEER, AS WELL AS SUCH STRIPING, PATCHING AND SHOULDER MAINTENANCE WHICH WILL PROVIDE SAFE AND CONVENIENT CONDITIONS AT ALL TIMES FOR THE PUBLIC.
- 9. THE CONTRACTOR SHALL IMMEDIATELY REPAIR ALL DAMAGE TO ANY FACILITY, EQUIPMENT, CABLE, WIRE, PAVEMENT, OR OTHER STRUCTURE CAUSED BY HIS OPERATION WITH ACCEPTABLE SUITABLE MATERIALS, TO ORIGINAL (PRE-CONSTRUCTION) OR BETTER CONDITION AND TO THE SATISFACTION OF THE ENGINEER, AT NO COST TO THE OWNER.
- 10. ANY ITEM NOT DESIGNATED TO BE REMOVED OR ANY EXISTING STRUCTURES, I.E. FENCE, GATE, PAVEMENT, LAWN, TREES, OR SHRUBBERY, AND ANY OTHER ITEM DISTURBED WITHIN CONSTRUCTION SERVITUDE OR OUTSIDE PROJECT ROW SHALL BE REPLACED TO ORIGINAL CONDITION AT NO COST TO THE OWNER.

TRAFFIC CONTROL:

- 1. PRIOR TO THE BEGINNING OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT FOR APPROVAL A PLAN FOR PROPOSED ROUTE IN WHICH CONSTRUCTION MATERIALS AND EQUIPMENT ARE TO BE TRANSPORTED TO AND FROM THE CONSTRUCTION SITE
- 2. THE CONTRACTOR SHALL SEEK APPROVAL OF THE ENGINEER FOR ANY TRAFFIC RELATED PLAN CHANGES, INCLUDING REMOVAL, RELOCATION, OR ADDITION OF THE CONTROL DEVICES BEFORE OR DURING THE COURSE OF THE CONSTRUCTION.
- 3. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE CONSTRUCTION SITE, AS WELL AS ALL REMAINING TRAFFIC CONTROL DEVICES, IN GOOD CONDITION. ALL REMOVED TRAFFIC CONTROL DEVICES SHALL BE RESTORED TO THEIR ORIGINAL POSITION AND ORIENTATION BY THE CONTRACTOR PRIOR TO THE TIME OF FINAL INSPECTION. (NO DIRECT PAY)
- 4. ALL TRAFFIC CONTROL DEVICES AND THEIR ASSOCIATED HARDWARE (SIGNS, SIGNALS, CONDUITS, CABLES, AND MARKINGS, ETC.) REMOVED OR DAMAGED DURING EXECUTION OF THIS CONTRACT SHALL BE REPLACED AT NOT COST TOT EH OWNER.
- 5. ANY DAMAGE CAUSE BY THE CONTRACTOR'S WORK SHALL BE IMMEDIATELY REPORTED BY THE CONTRACTOR TO THE OWNER. REPAIR SHALL BE PERFORMED BY THE CONTRACTOR AT THE DISCRETION OF THE OWNER WITH ALL ASSOCIATED COSTS PAID BY THE CONTRACTOR.

STOCKPILE MATERIAL:

- 1. ALL UNUSABLE MATERIALS SUCH AS DEBRIS, SOIL, TRASH, VEGETATION, AND OTHER MATERIALS SHALL BE REMOVED FROM THE STOCKPILE BEFORE LOADING THE STONE MATERIAL FOR RELOCATION.
- 2. THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND OWNER WHEN UNLOADING THE RELOCATED STONE MATERIAL AT THE PROPOSED DROP OFF SITE.
- 3. DELIVERED STONE SHALL BE UNLOADED IN A NEAT AND CONCISE MANNER TO MINIMIZE THE OVERALL FOOTPRINT OF THE DELIVERED MATERIAL.
- 4. THE CONTRACTOR SHALL PROVIDE DAILY TRUCK LOAD TICKETS INDICATING MATERIAL TYPE, NUMBER OF LOADS, AND NUMBER OF TONS OF MATERIAL RELOCATED.
- 5. THE CONTRACTOR SHALL STOCKPILE ALL UNUSABLE MATERIALS TO BE REMOVED AND DISPOSED OF AS GENERAL FXCAVATION

PAYMENT:

1. CONTRACTOR SHALL REQUEST PAYMENT AT THE CONTRACT UNIT PRICE FOR MATERIAL TRANSPORT UPON THE SUBMITTAL OF PAYMENT REQUESTS, INCLUDING DAILY TRUCK LOAD TICKETS TO THE CONTRACT MANAGER.

SUMMARY OF QUANTITIES			
Item	Item Description	Quantity	Unit
1	Material Transport	4000	Tons



| ENGINEERING LLC

Coastal Design & Infrastructure 4171 Essen Ln. | Ste. 700 Baton Rouge, Louisiana 70809 Phone: 225.406.0918

rente o pianistra o mbinosimental o

	REVISIONS	
No.	Description	Date



THIS DRAWING HAS
BEEN REDUCED TO

THIS DOCUMENT IS THE PROPERTY OF GRAND ISLE SHIP YARD ("GISY"). IT IS TO BE USED ONLY IN CONNECTION WITH WORK BEINS PERFORMED BY GISY OR THE APPROVED CONTRACTOR. REPRODUCTION IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN WORK PERFORMED BY GISY OR THE APPROVED CONTRACTOR IS FORBIDDEN EXCEPT BY EXPRESS WRITTEN FORMISSION OF GISY. IT IS TO BE SAFEGUARDED AGAINST BOTH DELIBERATE AND INADVERTENT JOISCLOSURE TO ANY THIND PARTY.

ST. TAMMANY PARISH

GOOSE POINT ARTIFICIAL REEFS

GENERAL NOTES

Project number	39130-1491
Date	SEPTEMBER 2024
Designed by	JSM
Drawn by	JSM
Checked by	TBB
Checked by	N/A
Plot Date	November 27, 2024

02



ENGINEERING LLC

Coastal Design & Infrastructure 4171 Essen Ln. | Ste. 700 Baton Rouge, Louislana 70809 Phone: 225.408.0918

nie o planininie o environimental consultt

REVISIONS		
No.	Description	Date



THIS DRAWING HAS BEEN REDUCED TO ONE HALF SIZE

THIS DOCUMENT IS THE PROPERTY OF GRAND ISLE SHIP YARD ("GISY"). IT IS TO BE USED ONLY IN CONNECTION WITH WORK BEING PERFORMED BY GISY OR THE APPROVED CONTRACTOR. REPRODUCTION IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN WORK PERFORMED BY GISY OR THE APPROVED CONTRACTOR IS FORBIDDEN EXCEPT BY EXPRESS WRITTEN PERMISSION OF GISY. IT IS TO BE SAFEGUARDED AGAINST BOTH DELIBERATE AND INADVERTENT DISCLOSURE TO ANY THIRD PARTY.

ST. TAMMANY PARISH

GOOSE POINT ARTIFICIAL REEFS

VICINITY MAP

25		
	Project number	39130-1491
0.	Date	SEPTEMBER 2024
П	Designed by	JSM
	Drawn by	JSM
	Checked by	TBB
	Checked by	N/A
	Plot Date	November 27, 2024

03

— HAUL ROUTE

1. LA 11 TO LA 90 IS THE SUGGESTED HAUL
ROUTE FROM THE STOCKPILE SITE TO 7500' 0
THE DROP OFF SITE.

THE CONTRACTOR MAY SUBMIT FOR APPROVAL AN ALTERNATE HAUL ROUTE.

14000' 21000'







ENGINEERING LLC

Coastal Design & Infrastructure 4171 Essen Ln. | Ste. 700 Baton Rouge, Louistana 70809 Phone: 225.408.0918

raks - planking - rivirokraftal coksi

REVISIONS		
No.	Description	Date



THIS DRAWING HAS BEEN REDUCED TO ONE HALF SIZE

THIS DOCUMENT IS THE PROPERTY OF GRAND ISLE SHIP YARD ("GISY"), IT IS TO BE USED ONLY IN CONNECTION WITH WORK BEING PERFORMED BY GISY OR THE APPROVED CONTRACTOR. REPRODUCTION IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN WORK PERFORMED BY GISY OR THE APPROVED CONTRACTOR IS FORBIDDEN EXCEPT BY EXPRESS WRITTEN PERMISSION OF GISY. IT IS TO BE SAFEGUARDED AGAINST BOTH DELIBERATE AND INADVERTENT DISCLOSURE TO ANY THIRD PARTY.

ST. TAMMANY PARISH

GOOSE POINT ARTIFICIAL REEFS

EXISTING STOCKPILE SITE

Project number	39130-1491
Date	SEPTEMBER 2024
Designed by	JSM
Drawn by	JSM
Checked by	TBB
Checked by	N/A
Plot Date	November 27, 2024

04

THE IMAGE ABOVE IS A GENERAL REPRESENTATION OF THE WORK AREA, ACTUAL FIELD CONDITIONS MAY DIFFER.



ENGINEERING LLC

171 Essen Ln. | Ste. 700 aton Rouge, Louisiana 70809 none: 225.408.0918

- Literature - menumbulan

REVISIONS		
No.	Description	Date



S DRAWING HAS IN REDUCED TO NE HALF SIZE

THIS DOCUMENT IS THE PROPERTY OF GRAND ISLE SHIP YARD ("GISY"), IT IS TO BE USED ONLY IN CONNECTION WITH WORK BEING PERFORMED BY GISY OR THE APPROVED CONTRACTOR. REPRODUCTION IN WHOLE OR IN PART FOR ANY DURPOSE OTHER THAN WORK PERFORMED BY GISY OR THE APPROVED CONTRACTOR IS FORBIDDEN EXCEPT BY EXPRESS WRITTEN PERMISSION OF GISY. IT IS TO BE SAFEGUARDED AGAINST BOTH DELIBERATE AND INADVERTENT DISCLOSURE TO ANY THIRD PARTY.

ST. TAMMANY PARISH

GOOSE POINT ARTIFICIAL REEFS


STOCKPILE LAYOUT

Project number	39130-1491
Date	SEPTEMBER 2024
Designed by	JSM
Drawn by	JSM
Checked by	TBB
Checked by	N/A
Plot Date	November 27, 2024

05

0' 30' 60' 90'

THE IMAGE ABOVE IS A GENERAL REPRESENTATION OF THE WORK AREA, ACTUAL FIELD CONDITIONS MAY DIFFER.





ENGINEERING LL

castal Design & Infrastructure 171 Essen L.n. | Ste. 700 aton Rouge, Louislana 70800 hone: 225.408.0018

erric o planistic o establishmental consu

REVISIONS		
No.	Description	Date



HIS DRAWING HAS EEN REDUCED TO ONE HALF SIZE

THIS DOCUMENT IS THE PROPERTY OF GRAND ISLI SHIP YARD ("GISY"). IT IS TO BE USED ONLY IN CONNECTION WITH WORK BEINP PERFORMED BY GISY OR THE APPROVED CONTRACTOR. REPRODUCTION IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN WORK PERFORMED BY GISY OR THE APPROVED CONTRACTOR IS GISY OR THE APPROVED CONTRACTOR IS PERMISSION OF GISY. IT IS TO BE SAFEGUARDED AGAINST BOTH DELIBERATE AND INADVERTENT DISCLOSURE TO ANY THIRD PARTY.

ST. TAMMANY PARISH

GOOSE POINT ARTIFICIAL REEFS

STOCKPILE SECTIONS

ı	Project number	39130-1491	
l	Date	SEPTEMBER 2024	
1	Designed by	JSM	
ı	Drawn by	JSM	
ı	Checked by	TBB	
ı	Checked by	N/A	
L	Plot Date	November 27, 2024	

06



THE IMAGE ABOVE IS A GENERAL REPRESENTATION OF THE WORK AREA, ACTUAL FIELD CONDITIONS MAY DIFFER. NOTES:

 CONTRACTOR SHALL COORDINATE WITH PONTCHARTRAIN MATERIALS CORPORATION PERSONNEL TO DETERMINE DROP OFF POINT FOR HAUL MATERIAL.





ENGINEERING LLC

Coastal Design & Infrastructure 4171 Essen Ln. | Ste. 700 Baton Rouge, Louislane 70809 Phone: 225.408.0918

ruks o plankinis o ekvironintektal soksi

REVISIONS		
No.	Description	Date



THIS DRAWING HAS BEEN REDUCED TO ONE HALF SIZE

THIS DOCUMENT IS THE PROPERTY OF GRAND ISLE SHIP YARD ("GISY"). IT IS TO BE USED ONLY IN CONNECTION WITH WORK BEING PERFORMED BY GISY OR THE APPROVED CONTRACTOR. REPRODUCTION IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN WORK PERFORMED BY GISY OR THE APPROVED CONTRACTOR IS FORBIDDEN EXCEPT BY EXPRESS WRITTEN PERMISSION OF GISY. IT IS TO BE SAFEGUARDED AGAINST BOTH DELIBERATE AND INADVERTENT DISCLOSURE TO ANY THIRD PARTY.

ST. TAMMANY PARISH

GOOSE POINT ARTIFICIAL REEFS

DROP OFF SITE MAP

		1 :
Project number	39130-1491	3
Date	SEPTEMBER 2024	Daniel 1 1101
Designed by	JSM	ш.
Drawn by	JSM	
Checked by	TBB	ď
Checked by	N/A	I.
Plot Date	November 27, 2024	Š

07