



## ST. TAMMANY PARISH

MICHAEL B. COOPER  
PARISH PRESIDENT

**February 19, 2025**

Please find the following addendum to the below-mentioned QUOTE.

**Addendum No.: 1**

**Quote#:** 25-5-1

**Project Name:** 102 Castle Dr

**Quote Due Date:** Thursday, February 27, 2025

### **GENERAL INFORMATION:**

---

1. Please remove Attachment A - Project Specifications and replace it with Attachment A - Project Specifications - Revised (attached).

### **ATTACHMENTS:**

---

1. Attachment A - Project Specifications Revised.pdf

**End of Addendum # 1**

| Item         | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |  | Length | Width | Quantity | Unit        |
|--------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--------|-------|----------|-------------|
|              | <b>General Notes:</b><br>1. Contractor shall field verify all quantities and measurements.<br>2. Contractor shall be responsible for locating and protecting all existing utilities.<br>3. Two-way traffic shall be maintained at all times during construction.<br>4. Basin and culverts shall be dewatered at no direct pay.<br>5. All existing sewer lines shall be tied-in at no direct pay.<br>6. Any <u>additional work</u> performed by the contractor <u>without prior written approval</u> from the St Tammany Parish Department of Public Works, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |  |        |       |          |             |
|              | <b>Project Summary:</b> All labor and materials necessary to replace catch basin and concrete sidewalk.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |  |        |       |          |             |
| 727-01       | <b>Mobilization:</b> All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site. Mobilization costs shall follow rules called out in the LA DOTD Standard Specifications for Roads and Bridges, Sec. 727.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |  |        |       | 1        | Lump Sum    |
| 702-03-00600 | <b>Catch Basin (CB-07) Curb Inlet:</b> All labor, materials, equipment and supervision necessary to <b>remove existing</b> , furnish, and install <b>new</b> catch basin in accordance with 2016 LADOTD Standard Specifications for Roads and Bridges, Section 702, and in conformity with lines and grades shown on the plans. Shop drawings of precast catch basin structures shall be provided to St. Tammany Parish Department of Public Works and approved prior to installation. All catch basins shall have 2’ BY 4’ frame and top. <b>Catch Basin shall be pre-cast concrete or concrete formed in place only.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |  | 4’     | 2’    | 1        | Each        |
| 706-01-00100 | <b>Remove and Replace Concrete Sidewalk:</b> All labor, materials, equipment and supervision necessary to, in accordance with these specifications, Remove/Replace Concrete Sidewalk according to LA DOTD Standard Specifications for Roads and Bridges, Section 706 and Section 202.03(a), Latest Edition. <b>Contractor shall be responsible for removal of concrete and all unsuitable base materials to a depth of 4” below the bottom grade of the new 4” thick concrete sidewalk. Replacement base material shall be River Sand or Pumped Sand.</b> Base repair and/or patch is not limited to a square yardage quantity, but may include the entire panel if directed by Department of Public Works inspection staff. This item is at no direct pay. Prior to contractor pouring replacement concrete panel, base material shall be examined by project inspector. Contractor shall inspect the project site and bid accordingly. Panels identified for removal and replacement next to and/or adjacent to new panels shall be saw-cut along the adjoining edge. Any damage caused by contractor operations shall be repaired immediately at no direct pay. <b>Replacement sidewalk panels shall be Fiber reinforced, 4000psi, 4” thick concrete.</b> |  | 42’    | 4’    | 19       | Square Yard |