



Purchasing Office
P.O. Box 40197 • Lafayette, LA 70504-0197
Office: (337) 482-5396
Fax: (337) 482-5059

April 15, 2025

ADDENDUM NO. 2

PROPOSAL FOR FURNISHING ALL LABOR, MATERIALS, EQUIPMENT, TRANSPORTATION, SUPERVISION, PERMITS, ETC. NECESSARY FOR THE NIRC BUILDING 34 – AIR HANDLING UNIT AND CONTROLS REPLACEMENT, LOCATED AT THE UNIVERSITY OF LOUISIANA AT LAFAYETTE CAMPUS, LAFAYETTE, LOUISIANA.

Due May 1, 2025, at 10:00 AM Solicitation No. 25204 (R1626707)

The following is to be made part of the original specifications as though issued at the same time and shall be incorporated integrally therewith. This addendum shall be acknowledged on the BID FORM when submitted to the Purchasing Department by the bid due date/time.

For access to full information, specifications, bid forms, and addenda follow this link:

[Public Works, Construction, and Renovation Solicitations \(Title 38\) | Office of Purchasing \(louisiana.edu\)](#)

Item No. 1 – General

1. See Attachment A for pre-bid sign in sheet.

Item No. 2 – Change to Specifications

1. Reference Page 9 of 45, MEDICAL REQUIREMENTS; Contractor shall be required to provide TB and Measle information prior to construction as indicated at contractor's expense.
2. Working hours for the project shall be 7:30 a.m. to 4:00 p.m. Monday to Friday. The contractor shall coordinate 7 days in advance for work after hours, and weekends.

Item No. 3 – Change to Drawings

1. Reference Sheet M102, Detail 1 and 2; Add note 16 to existing chilled water riser into mechanical room at floor level to read " CONTRACTOR SHALL REPLACE EXISTING 4 INCH, CHILLED WATER SUPPLY AND RETURN VALVES (TOTAL OF 4). CONTRACTOR SHALL BE RESPONSIBLE FOR THE DRAINAGE AND REFILLING OF SYSTEM. COORDINATE WITH OWNER FOR ALL SHUTDOWN AND DRAINAGE REQUIREMENTS TO ACCOMMODATE VALVE REPLACEMENT."
2. Reference Sheet M102, Detail 1 and 2; Add note 17 to air handling unit drain pan to read " CONTRACTOR SHALL PROVIDE NEW DRAIN PAN SIZED LARGE ENOUGH TO ACCOMMODATE EQUIPMENT AND NEW CHILLED WATER PIPING, VALVES AND CIRCUIT SETTERS. CONTRACTOR SHALL VERIFY EXACT SIZE IN FIELD."
3. Reference Sheet M104, Add the attached REHEAT COIL SCHEDULE – See Attachment B. Test and Balance Contractor shall balance all existing reheat coils to indicated water flows. Coordinate all requirements with Controls Contractor.

Item No. 4 – Change to Questions Contact Information:

1. All questions shall be submitted via email to BidQuestions@louisiana.edu.

This is a public works bid. The addendum **MUST** be acknowledged with your bid on the BID FORM. For questions related to bidding these projects, please contact the UL Lafayette Purchasing Department at BidQuestions@louisiana.edu.

Kristi Montet
Director – Procurement and Travel
University of Louisiana at Lafayette
Department of Purchasing