



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

June 26, 2025

Please find the following addendum to the below-mentioned BID.

Addendum No. 2

Bid#: 25-19-2

Project Name: St. John Church Rd Bridge

Bid Due Date: Tuesday, July 1, 2025

QUESTIONS & ANSWERS:

Question #1: Just wanted to reach out and ask if there was any precast in this project if any. If I could get an answer, it would be greatly appreciated.

Answer #1: Just the piles are precast.

Question #2: On sheet 102, notes under CONCRETE FORMWORK, is a PE Stamp required for the "Forming Plans"?

Answer #2: No, a PE stamp is not required on the "Forming Plans".

Question #3: The powerlines appear to be in conflict with pile driving and form removal, even though the bridge is being located further away from the lines. Can they be de-energized or relocated?

Answer #3: Once the clearing is completed, they will be relocated by WST.

Question #4: Will resistivity testing be required on A1 concrete?



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

Answer #4: Please reference Section 13- Project Sampling and Testing Plan for the required test.

Question #5: Boring B-1 shows 3" existing asphalt and 7" concrete. What is the extent of the 7" concrete and shouldn't there be a bid item for that work?

Answer #5: There may be a small amount of soil cement; it would fall under general excavation.

Question #6: There's a bid item for Removal of Fence, but no new fence installation. Is that correct?

Answer #6: There is no new fence installation.

End of Addendum # 2