

CITY OF BATON ROUGE
PARISH OF EAST BATON ROUGE
DEPARTMENT OF ENVIRONMENTAL SERVICES

September 12, 2025

ADDENDUM NO. 3

TO: ALL BIDDERS

SUBJECT: **CENTAL WASTEWATER TREATMENT PLANT DEMOLITION PROJECT**
CITY-PARISH PROJECT NO. 14-TP-MS-016D

ORIGINAL BID DATE: Tuesday, September 16, 2025 at 2:00 PM

CURRENT BID DATE: Tuesday, September 23, 2025 at 2:00 PM

The following revisions shall be incorporated in and take precedence over any conflicting part of the original contract document:

PART 1 – UNIFORM CONSTRUCTION BID FORMS:

1. For paper sealed bidders, with reference to page UCBF 1 of 4 of Part 1, Uniform Construction Bid Forms, the Bidder shall indicate the receipt of this addendum in the space provided. For online Central Bidding bidders, an acknowledgement of this addendum will be prompted by the electronic bidding program prior to formally submitting the bid. **Failure to indicate the receipt of this addendum shall be cause for the bid to be rejected.**
2. Acting in accordance with Louisiana Revised Statutes 38:2212, (C) (1), the bid opening date is postponed by seven (7) calendar days. **Bids will be opened at 2:00 PM Tuesday, September 23, 2025 in Room 806 of City Hall**, in lieu of September 16, 2025.

PART 2 – SPECIAL PROVISIONS AND CONTRACT DOCUMENTS:

1. For paper sealed bidders, with reference to page UCBF 1 of 4 of Part 1, Uniform Construction Bid Forms, the Bidder shall indicate the receipt of this addendum in the space provided. For online Central Bidding bidders, an acknowledgement of this addendum will be prompted by the electronic bidding program prior to formally submitting the bid. **Failure to indicate the receipt of this addendum shall be cause for the bid to be rejected.**
2. Acting in accordance with Louisiana Revised Statutes 38:2212, (C) (1), the bid opening date is postponed by seven (7) calendar days. **Bids will be opened at 2:00 PM Tuesday, September 23, 2025 in Room 806 of City Hall**, in lieu of September 16, 2025.

SPECIFICATIONS

1. Revise Section 03651, Part 2, Section 2.02 Materials, Note F to state the following:

The unit weight of the flowable fill shall be 115 lb/ft³ (±10 lb).

COMMENTS AND QUESTIONS

1. Would the Owner allow the contractor to physically remove the pipes intended to be abandoned in lieu of installing flow fill?

Yes, physically removing the pipes would be allowed. Note that any buried piping that would remain because it is under and/or connected to a below grade structure must be flow filled. No voids shall remain upon completion of the project since the site is within 1,500 feet of the Mississippi River levee. Contractor shall adhere to the requirements for excavation and backfill as listed in the Letters of No Objection which are included in the attachments of the Specifications.

REVIEWED:



Obie E. Watts, III, P.E.

APPROVED:



Adam M. Smith, P.E.