

Attachment B – Vendor Requirements
RFx 3000025533

1. The Contractor shall furnish one 40 – 42 cubic yard compaction container, equipped with an appropriately sized ram, to be used by the Louisiana Workforce Commission (LWC), located at 1001 North 23rd Street in Baton Rouge, LA 70802, to dispose of paper and trash. Pick up of the container shall be upon request by the State Agency on an as-needed basis. The container shall be equipped with a warning light to warn the operator when the container is almost filled to capacity. Ram shall be operated by a key-start push-button type control, which shall be mounted in such a manner that allows the operator to safely and conveniently reach the controls.
2. Container and ram must be placed in a location where the maximum width allowed is 10 feet. The container and ram-companied length shall be no more than 33 feet. The electrical/mechanical connections must be adaptable to the on-site conditions or restrictions. The containers or ram must easily load from the side of the loading dock of 42 inches high. Ram must be equipped with a lockable cover to prevent unauthorized use and/or persons from falling into ram opening.
3. The body of the container shall consist of heavy-duty steel plating, welded and reinforced in such fashion to withstand reasonable use and handling. If the ram is stationary, installation shall be the responsibility of the Contractor.
4. Container shall be equipped with a cover, which will contain the trash as it is hauled away. Any spills, which will be considered to be the fault of the Contractor, shall be promptly cleaned up by the Contractor.
5. The Contractor shall furnish and maintain the container and ram at all times. The container and ram shall be painted with a good-quality metal paint.
6. The container and ram shall meet and be maintained in accordance with all Federal and Louisiana State Laws governing such containers.
7. When notified by 9:00 A.M. CT, the Contractor must pick up, dump, and return the container by 4:00 P.M. CT on the same day. If notified after 9:00 A.M. CT, the Contractor must pick up, dump and return by 12:00 noon on the next work day (excluding weekends and state holidays).