



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

May 8, 2026

Please find the following addendum to the below-mentioned QUOTE.

Addendum No.: 1

Quote#: 26-10-1

Project Name: Camp Salmen Nature Park Playground

Quote Due Date: Thursday, May 14, 2026

GENERAL INFORMATION:

1. The Project Classification for this project has been changed. Bidders shall hold one of the following Major LA License Classifications: **Building Construction and/or Limited Specialty Service**.
2. Please remove Page 3: Section 2.1 Scope of Work/Services and replace it with Page 3, Section 2.1 Scope of Work/Services – Revised.

QUESTIONS & ANSWERS:

Question 1. Will you require the integrated shade post to be recapped with the factory caps for each of the posts where the existing integrated shades will be removed for the new free-standing shade?

Answer 1. Yes.

Question 2. Can the orientation of the swings be reconfigured to meet a more efficient and surfacing cost savings design while also meeting the use zone rules and guidelines for swings?

Answer 2. Yes.

Question 3. Will you consider a mixture of swing seats to accommodate users of all ages and abilities. EX. (mix of belt, tot, and ADA seats) - In my opinion it would be a good idea to include a mix of different type of seats to accommodate all user, just as the play structure is intended for. **PART I: OVERVIEW 1.1 Background -the current request is for six let seats.**

Answer 3. Yes.



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

Question 4. What type of containment border will be required for the stone base under the new swings? Concrete? Wood?

Answer 4. The containment border shall be concrete.

Question 5. Will the pre-bid meeting notes be addressed in an addendum?

Answer 5. No, meeting notes will not be added to the addendum.

Question 6. **2.2 Period of Agreement states that: The time period for completion of the work is within sixty (60) calendar days from the date listed to commence work in the Notice to Proceed issued by the Parish.** *Requesting this be changed to (at minimum) 120 days. The lead time for shade manufacturing on a large custom size is 8-10 weeks once the contract documents have been executed for ordering purposes.*

Answer 6. The revised time period for completion of work shall be one hundred twenty (120) calendar days from the issuance of the Notice to Proceed issued by the Parish.

Question 7. On page 14 it states: The Contractor may be required to post in each direction a public information sign, 4' x 4' in size, at the location of the project containing information required by the Parish. The Parish will supply this information. Will these signs be required?

Answer 7. Signage is not required for this project.

Question 8. Clarification needed: Bid reads in PART I: OVERVIEW 1.1 Background St. Tammany Parish Government is requesting a Contractor to provide all labor, materials, and equipment to install approximately 5,651 square feet of turf over existing poured-in-place surfacing, as well as install 1,536 square feet of new turf and padding over a stone base. The Contractor shall also provide and install a 60'LX50'WX12'H Eave Hip Shade structure to cover the playground area, and install a 3 bay 8' swing frame with shade and swing set belt seats or comparable in the area with the new turf : Will we also provide the new swings, or have they already been purchased?

Answer 8. Yes, the Contractor shall provide the new swings.

Question 9. Regarding the swing, would it be acceptable to provide a 2-bay swing frame with integrated shade which would include 2 belt seats, 1 ADA seat and 1 toddler seat?

Answer 9. No, we are requesting a 3-bay, which would provide more swings.

Question 10. What is the timeline for completion?

Answer 10. Please refer to Answer #6.



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

Question 11. The dimensions of the shade structure do not cover as much of the structure as shown in the renderings in the bid. See images below. Please advise whether you would like to increase the size of the shade structure or keep it the dimensions as stated in the bid. If you plan to keep the same dimensions which portion of the existing playground structure would you like to prioritize covering with shade?



Answer 11. We want to keep the shade structure dimensions as stated in the bid documents. Increasing the dimensions would affect the quoted price, and no additional funds are available for this project. We plan to prioritize shading the portions of the existing playground structure that receive the most use and direct sun exposure.

ATTACHMENTS:

1. **Page 3: Section 2.1 Scope of Work/Services-Revised.pdf**

End of Addendum # 1

PART II: SCOPE OF WORK/SERVICES

2.1 Scope of Work/Services

Contractor Qualifications:

- Contractor should be licensed for Building Construction and/or Limited Specialty Service through the Louisiana Board of Contractors;
- Contractor **shall** be a Qualified Contractor with the National Playground Contractors Association Inc.;
- Contractor **shall** have a current certification as a Certified Recreation Installation Specialist (RISC) and Certified Playground Safety Inspector (CPSI) for at least one employee; and
- Installer **shall** carry the designation of a Certified Synthetic Turf Installer from the Synthetic Turf Council.

All qualifications and certifications **shall be submitted prior to the award.**

Turf Specifications:

Colors: Primary yarn – field green; Thatch yarn – fresh green and tan (colors vary with manufacturers)

Environmental: Meets EN71-3 (European Toy Standard) and EPA/ RCRA regulations for toxic waste and heavy metals

ADA Compliance: Pass

Grass Yarn: Monofilament with thatch

Grass Yarn Denier: 12,800 Total

Pile Height: 1" – 1.125 Tall

Grass Yarn Face Weight: 60 oz/sy

Tufting Gauge: 1/5 Inch

Processing: USA

Primary Backing: UV stabilized, multi-layer polyurethane

Drainage Rates: 40 Inches Per Hour

Reinforcement Coating: 20 oz/sy of high-grade polyurethane

Melting Point: Over 220° F

Infill:

TCool Cooling Infill or equal product. Apply cooling infill at a rate of 2lb per foot

Padding and fall protection regulations must be submitted by the Contractor ONLY. St. Tammany Parish Government will not provide any specifications for padding/fall protection due to differences in manufacturing requirements.

Warranty:

The Parish requires a fifteen **(15) year** manufacturer's warranty from the date of acceptance for guaranteed workmanship, UV stability, water/heat/frost resistance, grab-tear strength, drainage, grass yarn melt points, chemical and environmental regulations.