



## ST. TAMMANY PARISH

MICHAEL B. COOPER  
PARISH PRESIDENT

**July 13, 2026**

Please find the following addendum to the below-mentioned QUOTE.

**Addendum No.: 1**

**Quote #: 26-20-1**

**Project Name: Lafitte St Drainage**

**Quote Due Date:**

### **GENERAL INFORMATION:**

---

1. Please remove Attachment G – Layout and replace it with Attachment G- Layout – Revised (attached).
2. Please remove Attachment A – Unit Price Sheet and Attachment A – Project Specifications and replace it with Attachment A – Unit Price Sheet and Attachment A – Project Specifications – Revised (attached).
3. Please add Attachment H – Sewer Layout to the package.

### **QUESTIONS & ANSWERS:**

---

Question 1. The layout plans call for all catch basins to be CB-01 while the unit price form calls for the catch basins to be CB-02. Which would be necessary for the project?

**Answer 1. Please refer to General Information #1.**

Question 2. Is Attachment G the only plans available for the project or will more be provided?

**Answer 2. There are no other plans available for this project.**

Question 3. The Unit Price Form calls for (8) Catch Basins while the provided plans only show (7). Is the 8th catch basin extra or is there a spot for it to be installed.

**Answer 3. Please refer to General Information # 2.**



## ST. TAMMANY PARISH

MICHAEL B. COOPER  
PARISH PRESIDENT

Question 4. The first paragraph of Part IV: Performance calls for, "The Contractor shall submit to the Parish for approval, five copies of all shop drawings, which shall have been checked and stamped with the approval of Contractor and identified as the parish may require." But there's no other language in the specifications detailing what the shop drawings will be. Will they need to be drawings of the newly installed drainage pipes? Or will the winning bidder have to have stamped improved plans of the area created by an engineer? Please provide clarification of what is expected from the bidder.

**Answer 4. This is not applicable to this project.**

Question 5. Will a staging area be provided to store the large drainpipes or any machinery?

**Answer 5. No.**

Question 6. On Attachment G, a footnote describes sewer tie-ins at no direct pay. Do you have a detail of these sewer tie-ins or is it a general note that is not applicable to this job?

**Answer 6. Please refer to General Information #3.**

Question 7. Would you also add a question regarding if it will be the General Contractor's responsibility to coordinate with the homeowner's when their driveway will be under construction? And will the General Contractor need to provide road plates for continued service?

**Answer 7. Yes, it will be the Contractor's responsibility to coordinate with the homeowners. Please refer to the project specification, as each item listed has descriptions of what is needed and required.**


### ATTACHMENTS:

---

1. Attachment G- Layout – Revised.pdf
2. Attachment A – Unit Price Sheet and Attachment A – Project Specifications – Revised.pdf
3. Attachment H – Sewer Layout.pdf

### End of Addendum # 1

Attachment G - Revised



|  |  |
|--|--|
|  |  |
|--|--|

| Rev. No | Date | Description |
|---------|------|-------------|
|         |      |             |
|         |      |             |
|         |      |             |

St. Tammany Parish  
Department of Public Works  
P.O. Box 628 Covington, La. 70434  
Phone: (888) 686-2552  
E-mail: [enr@stpar.org](mailto:enr@stpar.org)



|             |       |
|-------------|-------|
| Project No. | Sheet |
| Date        |       |
| Scale       |       |
| Drawn By    |       |

HWY 59

Lafitte Street

Orleans Street

Lafitte Street

HWY 59

Existing 48" RCPA  
invert is 7.31

Existing 30" CPP to  
remain

Existing 30" CPP to  
remain. Invert is 8.26

Existing 18" CPP to  
be removed and  
replaced with 32" of  
30" RCPA

Existing 18" CPP to  
be removed and  
replaced with 24" of  
30" RCPA



St. Tammany Parish  
Department of Agriculture  
P.O. Box 638 Covington, LA 70434  
Phone (504) 886-2552  
Email: [info@aginfo.org](mailto:info@aginfo.org)



QUOTE  
UNIT PRICE FORM

TO:

St. Tammany Parish Government

21454 Koop Drive, Suite 2F

Mandeville, LA. 70471

(OWNER TO PROVIDE NAME AND ADDRESS OF OWNER)

QUOTE FOR:

Lafitte St Drainage

Quote No.: 26-20-1

(OWNER TO PROVIDE PROJECT NAME & OTHER IDENTIFYING INFO)

UNIT PRICES: This form shall be used for any & all work required by the Quote Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

|              |          |                                                                                  |            |                                                     |  |
|--------------|----------|----------------------------------------------------------------------------------|------------|-----------------------------------------------------|--|
| Description: |          | <input checked="" type="checkbox"/> BASE QUOTE   OR <input type="checkbox"/> ALT |            | Mobilization                                        |  |
| REF NO.:     | QUANTITY | UNIT OF MEASURE                                                                  | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |  |
| 727-01       | 1        | Lump Sum                                                                         |            |                                                     |  |
| Description: |          | <input checked="" type="checkbox"/> BASE QUOTE   OR <input type="checkbox"/> ALT |            | Temporary Signs and Barricades                      |  |
| REF NO.:     | QUANTITY | UNIT OF MEASURE                                                                  | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |  |
| 713-01       | 1        | Lump Sum                                                                         |            |                                                     |  |
| Description: |          | <input checked="" type="checkbox"/> BASE QUOTE   OR <input type="checkbox"/> ALT |            | Removal of Pipe                                     |  |
| REF NO.:     | QUANTITY | UNIT OF MEASURE                                                                  | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |  |
| 202-02-32120 | 175      | Linear Foot                                                                      |            |                                                     |  |
| Description: |          | <input checked="" type="checkbox"/> BASE QUOTE   OR <input type="checkbox"/> ALT |            | Storm Drain Pipe (24" RCPA Equivalent)              |  |
| REF NO.:     | QUANTITY | UNIT OF MEASURE                                                                  | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |  |
| 701-04-01040 | 64       | Linear Foot                                                                      |            |                                                     |  |

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

UNIT PRICES: This form shall be used for any & all work required by the Quote Documents & described as unit prices. Amounts shall be stated in figures & only in figures. **REVISED**

|                |                                                                                                   |                                                                                                                                                              |            |                                                     |
|----------------|---------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-----------------------------------------------------|
| Description:   |                                                                                                   | <input checked="" type="checkbox"/> BASE QUOTE    OR <input type="checkbox"/> ALT    Storm Drain Pipe (30" RCPA Equivalent)                                  |            |                                                     |
| REF NO.:       | QUANTITY                                                                                          | UNIT OF MEASURE                                                                                                                                              | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |
| 701-04-01060   | 472                                                                                               | Linear Foot                                                                                                                                                  |            |                                                     |
| Description:   |                                                                                                   | <input checked="" type="checkbox"/> BASE QUOTE    OR <input type="checkbox"/> ALT    Catch Basin (CB-02)                                                     |            |                                                     |
| REF NO.:       | QUANTITY                                                                                          | UNIT OF MEASURE                                                                                                                                              | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |
| 702-03-00200   | 7                                                                                                 | Each                                                                                                                                                         |            |                                                     |
| Description:   |                                                                                                   | <input checked="" type="checkbox"/> BASE QUOTE    OR <input type="checkbox"/> ALT    Remove/Replace Concrete Driveway (6")(72 Hr High Early)                 |            |                                                     |
| REF NO.:       | QUANTITY                                                                                          | UNIT OF MEASURE                                                                                                                                              | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |
| 706-02-00200-A | 25                                                                                                | Square Yard                                                                                                                                                  |            |                                                     |
|                | <input checked="" type="checkbox"/> BASE QUOTE    OR <input type="checkbox"/> ALT    Slab Sodding |                                                                                                                                                              |            |                                                     |
| REF NO.:       | QUANTITY                                                                                          | UNIT OF MEASURE                                                                                                                                              | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |
| 714-01-00700   | 300                                                                                               | Square Yard                                                                                                                                                  |            |                                                     |
| Description:   |                                                                                                   | <input checked="" type="checkbox"/> BASE QUOTE    OR <input type="checkbox"/> ALT    Driveways, Turnouts and Miscellaneous (Level A Superpave With PG 67-22) |            |                                                     |
| REF NO.:       | QUANTITY                                                                                          | UNIT OF MEASURE                                                                                                                                              | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |
| 502-01-00200   | 30                                                                                                | Ton                                                                                                                                                          |            |                                                     |
| Description:   |                                                                                                   | <input type="checkbox"/> BASE QUOTE    OR <input type="checkbox"/> ALT                                                                                       |            |                                                     |
| REF NO.:       | QUANTITY                                                                                          | UNIT OF MEASURE                                                                                                                                              | UNIT PRICE | UNIT PRICE EXTENSION<br>(Quantity times unit price) |
|                |                                                                                                   |                                                                                                                                                              |            |                                                     |

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

Adding sub-surface pipe to prevent further shoulder erosion and to preserve the edge of the roadway.


| Item         | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Length | Width | Quantity | Unit        |
|--------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-------|----------|-------------|
|              | <b>General Notes:</b> <div><div>1.</div><div>2.</div><div>3.</div><div>4.</div><div>5.</div></div> <div>Contractor shall field verify all quantities and measurements.</div> <div>Contractor shall be responsible for locating and protecting all existing utilities.</div> <div>Two-way traffic shall be maintained at all times during construction. Contractor shall have flagmen on both ends of work zone. If Police details are used for traffic control this does not take the place of flag men.</div> <div>Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved. Contractor shall maintain project and construction signs.</div> <div>All existing sanitary/storm sewer lines shall be tied-in at no direct pay.</div>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |        |       |          |             |
|              | <b>Project Summary:</b> All labor, materials, equipment and supervision necessary to remove/replace collapsed/failed drainage culverts install new catch basins, remove/replace asphalt/concrete driveways and aprons                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |        |       |          |             |
| 727-01       | <b>Mobilization:</b> All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |       | 1        | Lump Sum    |
| 713-01       | <b>Temporary Signs and Barricades:</b> All labor, materials, equipment and supervision necessary to furnish, install, maintain and remove temporary construction barricades, precast concrete barriers, lights, signals, pavement markings and signs, including project signs; providing flaggers; and complying with all other requirements regarding the protection of the work, workers and safety of the public. Unless otherwise noted in the plans or special provisions this work also includes traffic control management in compliance with contract documents and the Manual on Uniform Traffic Control Devices (MUTCD), including the installation, inspection, maintenance, and removal of all traffic control devices on the project. This item shall not be construed to relieve the contractor of responsibilities for the safety of the public, for liability in connection therewith, or compliance with State and local laws or ordinances. Signs, barricades, barriers, channelizing devices, pavement markings, etc., shall comply with plan details, the MUTCD and Section 713 of 2016 LADOTD Standard Specifications for Roads and Bridges, Latest Edition. Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved. |        |       | 1        | Lump Sum    |
| 202-02-32120 | <b>Removal of Pipe:</b> All labor, materials and equipment necessary to remove the existing culverts throughout the job site. All debris and material shall be removed from job site at no direct pay.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |        |       | 175      | Linear Foot |

Adding sub-surface pipe to prevent further shoulder erosion and to preserve the edge of the roadway.

| Item           | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Length | Width | Quantity | Unit        |
|----------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-------|----------|-------------|
| 701-04-01040   | <b>Storm Drain Pipe (24" RCPA Equivalent):</b> All labor, materials, equipment, and supervision necessary to remove the existing culverts and replace with new <b>24" RCPA</b> . Items shall include all required saw-cutting, excavation, backfill material and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Public Works Department personnel. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Storm drain pipe installation shall be in accordance with Section 701 of LADOTD Standard Specifications. <b>See the attached layout sheets</b>                                                                                            |        |       | 64       | Linear Foot |
| 701-04-01060   | <b>Storm Drain Pipe (30" RCPA Equivalent):</b> All labor, materials, equipment, and supervision necessary to remove the existing culverts and replace with new <b>30" RCPA</b> . Items shall include all required saw-cutting, excavation, backfill material and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Public Works Department personnel. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Storm drain pipe installation shall be in accordance with Section 701 of LADOTD Standard Specifications. <b>See the attached layout sheets</b>                                                                                            |        |       | 472      | Linear Foot |
| 702-03-00200   | <b>Catch Basin (CB-02):</b> All labor, materials, equipment and supervision necessary to furnish and install catch basin in accordance with LADOTD Standard Specifications for Roads and Bridges, Section 702. All catch basins shall have TYPE "C" grate. Catch Basin can be pre-cast, poured in place or bricked. Location will be on attached layout sheet.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |        |       | 7        | Each        |
| 706-02-00200-A | <b>Remove/Replace Concrete Driveway (6") (72Hr High Early):</b> All labor, materials, equipment and supervision necessary to, in accordance with these specifications, Remove/Replace Concrete Driveway in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 706 and Section 202.02, 2016 Latest Edition. Contractor shall be responsible for removal of all unsuitable base materials to a depth of 12" below the bottom grade of the new 6" thick concrete panel. Replacement material shall be river or pumped sand. Base repair and/or patch is not limited to a square yardage quantity, but may include the entire panel if directed by Public Works inspection staff. Concrete will be 4000# with micro fibers Any damage caused by contractor operations shall be repaired immediately at no direct pay. |        |       | 25       | Square Yard |
| 714-01-00700   | <b>Slab Sodding:</b> All labor, materials, equipment, and supervision to install slab sodding to disturbed or new areas. Plant, roll, and water the sod where needed. Water sod until rooted. Sod must be delivered and laid green free from brown spots. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, 2016 edition. Sod shall be replaced in kind.                                                                                                                                                                                                                                                                                                                                                                                                                                   |        |       | 300      | Square Yard |

Adding sub-surface pipe to prevent further shoulder erosion and to preserve the edge of the roadway.

| Item         | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Length | Width | Quantity | Unit |
|--------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-------|----------|------|
| 502-01-00200 | Driveways, Turnouts and Miscellaneous (Level A Superpave with PG 67-22): All labor, materials, equipment and supervision necessary to furnish and construct one or more courses of asphaltic concrete mixture applied in conformance with LA DOTD Standard Specifications for Roads and Bridges. Mixture shall be Type A Superpave according to the 2016 Edition of LA Standard Specifications for Roads and Bridges. Subject to the specifications herein, and corresponding to the mixture selected, equipment and processes shall adhere to Section 503 in the 2016 Edition of LA Standard Specifications for Roads and Bridges. The use of a LADOTD approves material transfer vehicle (MTV) is allowed but not required unless specified. Tie-ins shall be 8’ deep beginning at the edge of the new asphalt roadway. Driveways shall be paved to the back of ditch. If elevation of driveway is too high for new paving, it shall be milled. The use of a LADOTD approves material transfer vehicle (MTV) is allowed but not required unless specified. |        |       | 30       | Ton  |



### SEWER EFFLUENT PIPE TIE-IN