

**ADDENDUM NO. 3
TO THE BID DOCUMENTS FOR:**

**DELGADO COMMUNITY COLLEGE
WESTBANK, BUILDING 1 AND 2
ROOFING AND WINDOW WIND MITIGATION
2600 GENERAL MEYER AVE.
NEW ORLEANS, LOUISIANA 70119**

PROJECT NO. 40006-R0031505

September 10, 2026

I. Scope:

1. Addendum No. 3 is issued in accordance with the provisions of the general specifications for the referenced project and is now considered to be an integral part of those original plans, specifications and contract documents.
2. ADDENDUM NO. 3 has been issued and shall also be posted and distributed by e-mail to Plan Holders of Record.

This addendum contains the following items:

Clarifications to Specifications.

II. Clarifications to the Specifications:

Section 011000 -

1.8 OWNER-FURNISHED PRODUCTS B. 1. Carpet Squares: **Delete Spec Section 011000 1.8 B. 1. There are no carpet squares in the scope of work.**

Section 012200 -

A schedule of unit prices is listed; however, there is no unit price form. Are there unit prices on this project? **Delete Spec Section 012200, there are no unit prices in the job.**

Section 015000 -

Who is responsible for providing the informational submittals? **The General Contractor.** These are not items the contractor would have access to; will they be supplied to us? **No, items such as the layout area, temporary offices and storage shed locations etc. are items the GC will have.** Are the temporary office, its contents, and storage and fabrication sheds required for this project? **No**

Section 024119 -

Is the owner or the contractor responsible for removing, moving, and storing any items in the buildings for the completion of scope of work? **1.9 B1 Contractor is responsible.**

Section 051200 -

Does the fabricator and installer need to be AISC Certified, or can they just adhere to their quality standards?

Yes, certified per the specification section.

Section 075500 -

Is the new tapered Iso to be 3/16" per foot? It is usually 1/8" or 1/4", just wanted to clarify.

ADDENDUM NO. 002
DELGADO COMMUNITY COLLEGE

Yes, 3/16 as shown.

Specification 084113-

Both Kawneer Trifab 451T and IR 521T storefront systems are listed in the specification yet details in the drawings show only IR521T profiles. Please confirm if 451T is applicable to the project and if so, please confirm locations.

Delete the spec for Trifab 451T, it is not in the project.

Please confirm door stile and thermal requirements. (e.g., 350 Medium Stile vs. 500 Wide Stile; Non-Thermal vs. Thermal) Medium Stile with Thermal break.

Wind pressures noted in the specification differ from those provided on the Components and Cladding Chart in the Structural General Notes. Please confirm which are to be followed. Use the Components and Cladding Chart requirements on the structural page. Delete the pressure noted in the specification.

Specification 088000-

Specified glass type GL-1 references multiple Low E Coatings and coating locations. Please confirm coating required and if the industry standard location on the #2 surface of the insulating laminated unit is acceptable. Please also confirm if the intent is for Clear or Atlantica tinted glass. Clear glass with Solarban 67 Low E on the #2 surface is acceptable.

End of Addendum No. 3