



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

October 26, 2026

Please find the following addendum to the below-mentioned BID.

Addendum No.: 1

Bid#: 26-44-2

Project Name: Ozone Park Subdivision Drainage

Bid Due Date: Wednesday, November 4, 2026

GENERAL INFORMATION:

1. Please remove Section 03 – Specifications and Section 04 – Unit Price Form and replace them with Section 03 – Specifications – Revised and Section 04 – Unit Price Form – Revised. (attached)

QUESTIONS & ANSWERS:

Question 1. There is a separate Pipe Removal item for 410 LF, but the new pipe descriptions also include removal/replacement

Answer 1. Please refer to General Information #1.

Question 2. Several existing mailboxes appear to conflict with the proposed drainage installation. Please confirm the contractor is responsible for temporarily removing, relocating, and reinstalling these mailboxes, including posts and foundations. If required, please clarify which bid item will compensate the contractor for this work, or whether these costs are considered incidental to the drainage installation.

Answer 2. Please refer to General Information #1.



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

ATTACHMENTS:

1. **Section 03 – Specifications – Revised.pdf**
2. **Section 04 – Unit Price Form – Revised.pdf**

End of Addendum # 1

Driveway Culverts and Sub Surface Drainage on Orleans Ave

Revised

Item	Description	Length	Width	Quantity	Unit
	General Notes: <ul style="list-style-type: none">1. Contractor shall field verify all quantities and measurements.2. Contractor shall be responsible for locating and protecting all existing utilities.3. Two-way traffic shall be always maintained during construction. Contractor shall have flagmen on both ends of work zone. If Police details are used for traffic control this does not take the place of flag men.4. All existing sanitary/storm sewer lines shall be tied in at no direct pay.5. Any additional work performed by the contractor without prior written approval from St Tammany Parish Department of Public Works, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish.6. Sub Surface area will be attached on the aerial map.7. Driveway locations will be on aerial map.				
	Project Summary: All labor, materials, equipment and supervision necessary to Remove and Replace Driveway Culverts. Also, installing Sub Surface Drainage.				
727-01	Mobilization: All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site.			1	Lump Sum
713-01	Temporary Signs and Barricades: All labor, materials, equipment and supervision necessary to furnish, install, maintain and remove temporary construction barricades, precast concrete barriers, lights, signals, pavement markings and signs, including project signs ; providing flaggers; and complying with all other requirements regarding the protection of the work, workers and safety of the public. Unless otherwise noted in the plans or special provisions this work also includes traffic control management in compliance with contract documents and the Manual on Uniform Traffic Control Devices (MUTCD), including the installation, inspection, maintenance, and removal of all traffic control devices on the project. This item shall not be construed to relieve the contractor of responsibilities for the safety of the public, for liability in connection therewith, or compliance with State and local laws or ordinances. Signs, barricades, barriers, channelizing devices, pavement markings, etc., shall comply with plan details, the MUTCD and Section 713 of LADOTD Standard Specifications for Roads and Bridges, 2016 Edition. Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved.			1	Lump Sum

Driveway Culverts and Sub Surface Drainage on Orleans Ave

Item	Description	Length	Width	Quantity	Unit
510-01-00200	Full Depth Asphalt Patching (12") (Level 1 Superpave with PG 67-22): All labor, materials, equipment and supervision necessary to remove and replace asphalt pavement at locations specified by the Project Construction Manager/Project Inspector and in accordance with the 2016 LA DOTD Standard Specifications for Roads and Bridges, Section 510, LA DOTD 2016 Standard Specifications for Roads and Bridges. Mixture shall be Level 1 Superpave according to LA DOTD 2016 Standard Specifications for Roads and Bridges. Subject to the specifications herein, and corresponding to the mixture selected, equipment and processes shall adhere to Section 503 in the 2016 Edition of LA Standard Specifications for Roads and Bridges. The use of a LADOTD approves material transfer vehicle (MTV) is allowed but not required unless specified. All material shall be removed to minimum depth of 12" and replaced with a minimum 12" of asphalt. Removed materials, including large asphalt patches, shall be disposed of outside and away from the project site at no direct pay. The repaired asphalt shall have a smooth, uniform surface, free from ridges, waves, depressions or loose material. The re-compacted roadbed shall be primed in accordance with Section 505. The contractor shall protect the compacted roadbed from damage due to either public traffic or construction operations and shall always maintain the roadbed in satisfactorily condition, including the asphalt patch. Any damage shall be repaired immediately by the contractor at no direct pay. Patch shall be compacted in minimum 2 equal lifts.			60	Square Yard
701-04-01020	Storm Drain Pipe (18" Equivalent RCPA): All labor, materials and equipment necessary to remove/replace 18" Equivalent RCPA. Item shall include all required saw-cutting, excavation, backfill material and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Public Works Department personnel. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Storm drain pipe installation shall be in accordance with Section 701 of LADOTD Standard Specifications.			64	Linear Foot

Driveway Culverts and Sub Surface Drainage on Orleans Ave

Item	Description	Length	Width	Quantity	Unit
701-04-01040	Storm Drain Pipe (24" Equivalent RCPA): All labor, materials and equipment necessary to remove/replace 24" Equivalent RCPA. Item shall include all required saw-cutting, excavation, backfill material and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Public Works Department personnel. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Storm drain pipe installation shall be in accordance with Section 701 of LADOTD Standard Specifications.			168	Linear Foot
701-04-01080	Storm Drain Pipe (36" Equivalent RCPA): All labor, materials and equipment necessary to remove existing 36" CMP and install new 36" RCPA Equivalent. Item shall include all required saw-cutting, pipe removal, excavation, backfill material and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Engineering Department personnel. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Storm drain pipe installation shall be in accordance with Section 701 of LADOTD Standard Specifications. 2016 edition. See attached drawing for locations.			32	Linear Foot
701-04-01120	Storm Drain Pipe (48" Equivalent RCPA): All labor, materials and equipment necessary to remove existing 30" CMP and install new 48" RCPA Equivalent. Item shall include all required saw-cutting, pipe removal, excavation, backfill material and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Engineering Department personnel. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Storm drain pipe installation shall be in accordance with Section 701 of LADOTD Standard Specifications. 2016 edition. See attached drawing for locations.			104	Linear Foot
702-03-00100	Catch Basin (CB-01): All labor, materials, equipment and supervision necessary to furnish and install catch basin in accordance with LADOTD Standard Specifications for Roads and Bridges, Section 702, and in conformity with lines and grades shown on the plans. Shop drawings of precast catch basin structures shall be provided to St. Tammany Parish Department of Public Works and approved prior to installation. All catch basins shall have TYPE "C" grate. Catch Basin shall be pre-cast concrete or concrete formed in place only.			4	Each

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition 2016

Driveway Culverts and Sub Surface Drainage on Orleans Ave

Item	Description	Length	Width	Quantity	Unit
702-03-00200	Catch Basin (CB-02): All labor, materials, equipment and supervision necessary to furnish and install catch basin in accordance with LADOTD Standard Specifications for Roads and Bridges, Section 702, and in conformity with lines and grades shown on the plans. Shop drawings of precast catch basin structures shall be provided to St. Tammany Parish Department of Public Works and approved prior to installation. All catch basins shall have TYPE “C” grate. Catch Basin shall be pre-cast concrete or concrete formed in place only. See the attached layout sheets.			2	Each
706-02-00200	Remove/Replace Concrete Driveway (6”) (72-HR High Early): All labor, materials, equipment and supervision necessary to, in accordance with these specifications, Remove/Replace Concrete Driveway in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 706 and Section 202.02, 2016 Latest Edition. Contractor shall be responsible for removal of all unsuitable base materials to a depth of 12” below the bottom grade of the new 6” thick concrete panel. Replacement materials shall be river or pumped sand. Base repair and/or patch is not limited to a square yardage quantity but may include the entire panel if directed by Public Works inspection staff. Concrete will be 4000# with microfibers Any damage caused by contractor operations shall be repaired immediately at no direct pay.			50	Square Yard
714-01-00700	Centipede Sod: All labor, materials, equipment, and supervision to install slab sodding to disturbed or new areas. Plant, roll, and water the sod where needed. Water sod until rooted. Sod must be delivered and laid green free from brown spots.			100	Square Yard
502-01-00200	Driveways, Turnouts and Miscellaneous (Level A Superpave With PG 67-22): All labor, materials, equipment and supervision necessary to furnish and construct one or more courses of asphaltic concrete mixture applied in conformance with LA DOTD Standard Specifications for Roads and Bridges. Mixture shall be Type A Superpave according to the 2016 Edition of LA Standard Specifications for Roads and Bridges. Subject to the specifications herein, and corresponding to the mixture selected, equipment and processes shall adhere to Section 503 in the 2016 Edition of LA Standard Specifications for Roads and Bridges. The use of a LADOTD approves material transfer vehicle (MTV) is allowed but not required unless specified. Tie-ins shall be 8’ deep beginning at the edge of the new asphalt roadway. Driveways shall be paved to the back of ditch. If elevation of driveway is too high for new paving, it shall be milled. The use of a LADOTD approves material transfer vehicle (MTV) is allowed but not required unless specified.			45	Ton

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition 2016

Driveway Culverts and Sub Surface Drainage on Orleans Ave

Revised

Item	Description	Length	Width	Quantity	Unit
805-01-01000	Class A1 Concrete Headwalls: All labor, materials, equipment and supervision necessary to construct and install concrete headwalls. All headwalls are to be 6” thick and constructed of 4000psi concrete with fiber mesh. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Sec. 805. 2016 Latest Edition. Contractor shall use dowels to pin the headwalls to the concrete splash pad. All debris is to be removed at no direct pay. Location will be on the attached layout sheet.			3	Each

Driveway Culverts and Sub Surface Drainage on Walnut Street

Item	Description	Length	Width	Quantity	Unit
	General Notes: <ul style="list-style-type: none">1. Contractor shall field verify all quantities and measurements.2. Contractor shall be responsible for locating and protecting all existing utilities.3. Two-way traffic shall be always maintained during construction. Contractor shall have flagmen on both ends of work zone. If Police details are used for traffic control this does not take the place of flag men.4. All existing sanitary/storm sewer lines shall be tied in at no direct pay.5. Any additional work performed by the contractor without prior written approval from St Tammany Parish Department of Public Works, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish.6. Sub Surface area will be attached on the aerial map.7. Driveway locations will be on aerial map.				
	Project Summary: All labor, materials, equipment and supervision necessary to Remove and Replace Driveway Culverts. Also, installing Sub Surface Drainage.				
727-01	Mobilization: All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site.			1	Lump Sum
713-01	Temporary Signs and Barricades: All labor, materials, equipment and supervision necessary to furnish, install, maintain and remove temporary construction barricades, precast concrete barriers, lights, signals, pavement markings and signs, including project signs ; providing flaggers; and complying with all other requirements regarding the protection of the work, workers and safety of the public. Unless otherwise noted in the plans or special provisions this work also includes traffic control management in compliance with contract documents and the Manual on Uniform Traffic Control Devices (MUTCD), including the installation, inspection, maintenance, and removal of all traffic control devices on the project. This item shall not be construed to relieve the contractor of responsibilities for the safety of the public, for liability in connection therewith, or compliance with State and local laws or ordinances. Signs, barricades, barriers, channelizing devices, pavement markings, etc., shall comply with plan details, the MUTCD and Section 713 of LADOTD Standard Specifications for Roads and Bridges, 2016 Edition. Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved.			1	Lump Sum

Driveway Culverts and Sub Surface Drainage on Walnut Street

Revised

Item	Description	Length	Width	Quantity	Unit
701-04-01000	Storm Drain Pipe (15" RCPA Equivalent): All labor, materials and equipment necessary to remove/replace 15" Equivalent RCPA. Item shall include all required saw-cutting, excavation, backfill material, 3" compacted sand base and embankment. Item shall include removal and replacement of all unsuitable material as identified by St. Tammany Parish Public Works Department personnel and backfilled with Type A material under flexible pavement and Type B under Rigid pavement. All pipe joints shall be wrapped with suitable geotextile fabric. Contractor installed pipe shall be cleaned of all debris and other materials prior to final acceptance. Storm drainpipe installation shall be in accordance with Section 701 of 2016 LADOTD Standard Specifications			348	Linear Foot
702-03-00100	Catch Basin (CB-01): All labor, materials, equipment and supervision necessary to furnish and install catch basin in accordance with LADOTD Standard Specifications for Roads and Bridges, Section 702, and in conformity with lines and grades shown on the plans. Shop drawings of precast catch basin structures shall be provided to St. Tammany Parish Department of Public Works and approved prior to installation. All catch basins shall have TYPE "C" grate. Catch Basin shall be pre-cast concrete or concrete formed in place only.			8	Each
706-02-00200	Remove/Replace Concrete Driveway (6") (72-HR High Early): All labor, materials, equipment and supervision necessary to, in accordance with these specifications, Remove/Replace Concrete Driveway in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 706 and Section 202.02, 2016 Latest Edition. Contractor shall be responsible for removal of all unsuitable base materials to a depth of 12" below the bottom grade of the new 6" thick concrete panel. Replacement materials shall be river or pumped sand. Base repair and/or patch is not limited to a square yardage quantity but may include the entire panel if directed by Public Works inspection staff. Concrete will be 4000# with microfibers Any damage caused by contractor operations shall be repaired immediately at no direct pay.			170	Square Yard
714-01-00700	Centipede Sod: All labor, materials, equipment, and supervision to install slab sodding to disturbed or new areas. Plant, roll, and water the sod where needed. Water sod until rooted. Sod must be delivered and laid green free from brown spots.			100	Square Yard

Revised

Driveway Culverts and Sub Surface Drainage on Walnut Street

Item	Description	Length	Width	Quantity	Unit
502-01-00200	Driveways, Turnouts and Miscellaneous (Level A Superpave With PG 67-22): All labor, materials, equipment and supervision necessary to furnish and construct one or more courses of asphaltic concrete mixture applied in conformance with LA DOTD Standard Specifications for Roads and Bridges. Mixture shall be Type A Superpave according to the 2016 Edition of LA Standard Specifications for Roads and Bridges. Subject to the specifications herein, and corresponding to the mixture selected, equipment and processes shall adhere to Section 503 in the 2016 Edition of LA Standard Specifications for Roads and Bridges. The use of a LADOTD approves material transfer vehicle (MTV) is allowed but not required unless specified. Tie-ins shall be 8’ deep beginning at the edge of the new asphalt roadway. Driveways shall be paved to the back of ditch. If elevation of driveway is too high for new paving, it shall be milled. The use of a LADOTD approves material transfer vehicle (MTV) is allowed but not required unless specified.			30	Ton
S-00001	Driveway Material (gravel): All labor, material, equipment and supervision necessary to provide and install new driveway material in the gravel driveways/parking lots. Material shall be graded to drain off each end of the driveway/parking area.			20	Cubic Yard

Revised

(OWNER TO PROVIDE NAME AND ADDRESS OF OWNER)

26-44-2

(OWNER TO PROVIDE PROJECT NAME & OTHER IDENTIFYING INFO)

UNIT PRICES: This form shall be used for any & all work required by the Quote Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description:	☒ BASE QUOTE	OR	☐ ALT	Mobilization	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
727-01	1	Lump Sum			
Description:	☒ BASE QUOTE	OR	☐ ALT	Temporary Signs and Barricades	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
713-01	1	Lump Sum			
Description:	☒ BASE QUOTE	OR	☐ ALT	Full Depth Asphalt Patching (12") (Level 1 Superpave with 67-22)	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
510-01-00200	60	Square Yard			
Description:	☒ BASE QUOTE	OR	☐ ALT	Storm Drain Pipe (15" Equivalent RCPA)	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
701-04-01000	348	Linear Foot			

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

UNIT PRICES: This form shall be used for any & all work required by the Quote Documents & described as unit prices. Amounts shall be stated in figures & only in figures. Revised

Description: ☒ BASE QUOTE OR ☐ ALT Storm Drain Pipe (18" Equivalent RCPA)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
701-04-01020	64	Linear Foot		
Description: ☒ BASE QUOTE OR ☐ ALT Storm Drain Pipe (24" Equivalent RCPA)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
701-04-01040	168	Linear Foot		
Description: ☒ BASE QUOTE OR ☐ ALT Storm Drain Pipe (36" Equivalent RCPA)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
701-04-01080	32	Linear Foot		
Description: ☒ BASE QUOTE OR ☐ ALT Storm Drain Pipe (48" Equivalent RCPA)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
701-04-01120	104	Linear Foot		
Description: ☒ BASE QUOTE OR ☐ ALT Catch Basin (CB-01)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
702-03-00100	12	Each		
Description: ☒ BASE QUOTE OR ☐ ALT Catch Basin (CB-02)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
702-03-00200	2	Each		

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

UNIT PRICES: This form shall be used for any & all work required by the Quote Documents & described as unit prices. Amounts shall be stated in figures & only in figures. Revised

Description: ☒ BASE QUOTE OR ☐ ALT Remove/Replace Concrete Driveway (6")(72Hr High Early)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
706-02-00200	220	Square Yard		
Description: ☒ BASE QUOTE OR ☐ ALT Centipede Sod				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
714-01-00700	200	Square Yard		
Description: ☒ BASE QUOTE OR ☐ ALT Driveways, Turnouts and Miscellaneous (Level A Superpave With PG 67-22)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
502-01-00200	75	Ton		
Description: ☒ BASE QUOTE OR ☐ ALT Class A1 Concrete Headwalls				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
805-01-01000	3	Each		
Description: ☒ BASE QUOTE OR ☐ ALT Driveway Material (gravel)				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
S-00001	20	Cubic Yard		
Description: ☐ BASE QUOTE OR ☐ ALT				
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.