CITY OF BATON ROUGE
PARISH OF EAST BATON ROUGE

November 13, 2026

ADDENDUM NO. 1

TO: **ALL BIDDERS**

SUBJECT: **CORA DRIVE (Goodwood Blvd. To Florida Blvd.) SIDEWALK IMPROVEMENTS**
CITY-PARISH PROJECT NO. 24-EN-HC-0025

ORIGINAL BID DATE: TUESDAY, NOVEMBER 17, 2026 at 2:00 P.M.
REVISED DATE BY THIS ADDENDUM, THURSDAY, NOVEMBER 19, 2026 @ 2:00 P.M.

The following revisions shall be incorporated in and take precedence over any conflicting part of the original contract documents.

REQUESTS FOR INFORMATION AND RESPONSES

As of October 19, 2026, we received few questions that we should address but more time is needed to address them and the bid open date is therefore revised accordingly.

1. Will there be an item needed to cover possible Offsets needed for the existing utility lines, or will that need to be covered in an existing item?

    - ***No. There are existing Bid Items 1112100 "ADJUSTING VALVE BOXES & RELOCATE WATER METERS" and 1112104 "ADJUSTING WATER SPIGOT". Refer to Note 1 on Sheets 10 and 11 for additional direction. The field-verification and coordination work described therein are at No Direct Pay. Any necessary adjustments/relocations will be performed by others.***

2. Do you know how many actual signs are there to be installed? I see notes in the plans like "Required Relocated Stop Sign with All way plaque." I think I've only found two that don't say "Relocated". I am thinking that it means that we are installing all new and relocated but it doesn't specify. If so, then are we installing all new signs or are we reusing the existing ones that are to be relocated?

    - ***Bid Items 9900073 "RELOCATION OF EXIST. ROAD SIGN" (24 EACH) and 9900091 "RELOCATION AND ADJUSTMENT OF MONUMENT SIGN AND BEDDING" (1 EACH) are the only identified scope of signs to be relocated. This indicates that the existing sign is to be relocated and re-installed at the proposed location. Bid Item 9050200 "TRAFFIC SIGNS" (14.75 SQ. FT.) is the only identified scope of signs to be installed. This indicates that a new sign is to be furnished and installed at the proposed location. The installation of new signs is shown on the Plans in two locations:***
        - ***Sheet 6: R1-1 STOP sign with R1-3P ALL WAY plaque.***
        - ***Sheet 9: R1-1 STOP sign.***

George Chike, P.E.
Project Manager